



OFFICE OF CHIEF DISTRICT MEDICAL AND PUBLIC HEALTH OFFICER, GAJAPATI
PARALAKHEMUNDI

E-mail : gajapatidmo@gmail.com, Ph: (06815)-222205/222305/223834



NO: 1758

Date: 02/03/2023

The CDM&PHO Officer, Gajapati invites Sealed percentage rate bid on behalf of Government of Odisha from registered and eligible Civil Contractors of the State PWD (R&B)/Water Resource/Rural Works/M.I./C.P.W.D. conformity with the DTCN are invited from the "C"&"D" Class contractors for execution of works under ZSS as detailed in **Annexure-I**. The tender document (**BOQ**) can be obtained from district **NIC Website (www.gajapati.nic.in)** from **Dt-04.03.23 to 14.03.23 till 5.30P.M.** The tender document (**BOQ**) duly signed by the Contractors should be accompanied with the self attested photo copy of valid GST Clearance certificate, PAN card, Registration Certificate and requisite EMD in shape of Demand Draft drawn in favour of CDM&PHO Gajapati" payable at "Paralakhemundi" from any Nationalized Bank and NSC/ KVP/ Time Deposit duly pledged. The tender document (**BOQ**) should accompanied with requisite tender paper cost in shape of Demand Draft drawn in favour of CDM&PHO Gajapati" payable at "Paralakhemundi" from any Nationalized Bank. The tenders will be received up to Dt-**15.03.23 till 5.30 p.m.** and addressed to O/o CDM&PHO, Gajapati, 761200 through **Registered/Speed Post only**. The tender to be opened on **Dt 16.03.23 at 11.00 A.M.** at office chamber of CDM&PHO Gajapati, in presence of the tenderers or their authorized representatives. All bidders shall have to submit an affidavit in support of authenticity of documents/ credentials. The detail terms and conditions can be seen at **NIC Website (www.gajapati.nic.in)**. The name of the work should be written on the **top of the envelope**. The undersigned reserves the right to cancel the tender without assigning any reason thereof.

CDM&PHO Gajapati

ANNEXURE-I

Sl. No.	Name of the work	Scheme	Est. Cost put to tender in Rs.	EMD	Cost of Tender Paper in Rs.	Period of Completion & Class of Contractor
1.	STRENGTHING OF INFRASTRUCTURE OF SUB CENTRE HEALTH WELNESS CENTRE AT MULIGUMMA UNDER RAYAGADA BLOCK	NHM	8,43,277.98	8500.00	4000.00	6 Months C&D class contractor

CDM&PHO Gajapati

Memo No: 1759

Date: 02/03/2023

Copy to the DIO, NIC, Gajapati for information and requested to upload the tender call notice and detail tender documents in the district NIC website for information of the public/prospective bidders from **10.00 A.M. of 04.03.2023 to 5.30 P.M. of 14.03.2023.**

CDM&PHO, Gajapati



OFFICE OF CHIEF DISTRICT MEDICAL AND PUBLIC HEALTH OFFICER, GAJAPATI
PARALAKHEMUNDI



E-mail : gajapaticdmo@gmail.com, Ph: (06815)-222205/222305/223834

Memo No: 1760

Date: 02/03/2023

Copy forwarded to the Joint Director(Advertisement), I & P.R. Department Govt. of Odisha, Bhubaneswar with a request to publish the Tender Call Notice in two odia daily widely circulated news paper in all Odisha edition in minimum space for one day and the complementary copies of the News paper may be sent to this Office for reference and record.

[Signature]
CDM&PHO, Gajapati
2.3.23

Memo No: 1761

Date: 02/03/2023

Copy to PA to Collector, Gajapati / CDO-CUM-EO, ZP Gajapati for favour of kind information and necessary action.

[Signature]
CDM&PHO, Gajapati
2/3/23

Memo No: 1762

Date: 02/03/2023

Copy to PA, ITDA, Gajapati, /Sub-Collector, Paralakhemundi, Gajapati / All Block Development Officer of Gajapati/DSWO, Gajapati/DEO, Gajapati/CDM & PHO, Gajapati for information with a request to display the Tender Call Notice on their notice board for information of public.

[Signature]
CDM&PHO, Gajapati
2.3.23

Memo No: 1763

Date: 02/03/2023

Copy to all tender committee members for information and requested to present for opening of the tenders in the given date, time & venue.

[Signature]
CDM&PHO, Gajapati
2.3.23

BILL OF QUANTITY

Name of the work

DETAIL ESTIMATE FOR STRENGTHING OF
INFRASTRUCTURE OF SUB CENTRE HEALTH WELNESS
CENTRE AT MULIGUMMA UNDER RAYAGADA BLOCK

Estimated Cost

9,98,068.00

Amount Put to Tender

843,277.98

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
1	Earth work in all kinds of soil within 50m. Initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm.to 7cm. and laying in layers not exceeding 0.3 m. in depth as per direction of the Engineer-in-charge.	81.39	CUM	219.78	17887.89	Rupees Seventeen Thousand Eight Hundred EightySeven Paise EightyNine Only
2	Filling foundation and plinth with sand and wel watered & rammed etc . Complete including cost of sand .	70.81	CUM	385.95	27329.12	Rupees TwentySeven Thousand Three Hundred TwentyNine Paise Twelve Only
3	Cement Concrete (1:4:8) by using 4cm. Size B.H.G. metal including cost, conveyance etc. complete.	19.21	CUM	3770.89	72438.80	Rupees SeventyTwo Thousand Four Hundred ThirtyEight Paise Eighty Only
4	Cement concrete (1:2:4) with 12mm. Size hard broken granite chips (Hand broken) including all cost, conveyance , royalty etc. complete.	2.10	CUM	5451.53	11448.21	Rupees Eleven Thousand Four Hundred FourtyEight Paise TwentyOne Only
5	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. ROOF SLAB	0.60	CUM	9094.62	5456.77	Rupees Five Thousand Four Hundred FiftySix Paise SeventySeven Only
6	Supplying fitting and placing un coated HYSD Bars reinforcement complete as per drawing and Technical specification. overlaps couplings, welded joints, space bars, chairs stay, hangers, annealed steel wires shall not be measured for payment.	0.60	QNT L	9210.40	5526.24	Rupees Five Thousand Five Hundred TwentySix Paise TwentyFour Only
7	Fly ash brick masonary in cement mortar (1:6) by using 9" size C.B.Bricks including all cost, conveyance etc. complete.	5.40	CUM	4359.84	23543.14	Rupees TwentyThree Thousand Five Hundred FourtyThree Paise Fourteen Only
8	12mm thick cement plaster (1:6) for out side plaster.	67.13	SQM	142.29	9551.93	Rupees Nine Thousand Five Hundred FiftyOne Paise NinetyThree Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
9	20 mm thick cement plaster (1:6) for stone work. Per 1 Sqm.	33.67	SQM	213.57	7190.90	Rupees Seven Thousand One Hundred Ninety Paise Ninety Only
10	Providing and fixing Ceramic tiles in dados, skirtings and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles as directed by the Engineer-in-charge.	30.98	SQM	719.15	22279.27	Rupees TwentyTwo Thousand Two Hundred SeventyNine Paise TwentySeven Only
11	Providing and fixing Ceramic tiles in floors, treads or steps and landing on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles .	7.62	SQM	742.19	5655.49	Rupees Five Thousand Six Hundred FiftyFive Paise FourtyNine Only
12	Painting two coat with any approved paint over a coat of primer on iron works	73.94	SQM	140.34	10376.74	Rupees Ten Thousand Three Hundred SeventySix Paise SeventyFour Only
13	Distempering Two coat over a coat of white washing including cost conveyance labour & T&P etc complete.	430.33	SQM	66.28	28522.27	Rupees TwentyEight Thousand Five Hundred TwentyTwo Paise TwentySeven Only
14	supply of MS shutter	196.00	kg	62.00	12152.00	Rupees Twelve Thousand One Hundred FiftyTwo Only
15	Painting two coats with weather seal paint over a coat of primer including cost, conveyance all materilas, labour and T & P etc complete.	134.07	SQM	135.78	18204.02	Rupees Eighteen Thousand Two Hundred Four Paise Two Only
16	Finishing wall surface with wall putty (water base) of appvd quality and make and finished smooth even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour with T&P etc complete in all resoect.	134.07	SQM	94.65	12689.73	Rupees Twelve Thousand Six Hundred EightyNine Paise SeventyThree Only
17	Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2.	105.45	CUM	128.91	13593.56	Rupees Thirteen Thousand Five Hundred NinetyThree Paise FiftySix Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
18	Supplying & Fixing of precast interlocking cement concrete block 80mm thick , grading strength of any individual should not less than 40nos/sqm as per drawing	248.04	SQM	1115.60	276713.42	Rupees Two Lakh SeventySix Thousand Seven Hundred Thirteen Paise FortyTwo Only
	Compound wall					
19	Earth work in all kinds of soil within 50m. Initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm.to 7cm. and laying in layers not exceeding 0.3 m. in depth as per direction of the Engineer-in-charge.	47.94	CUM	219.78	10536.25	Rupees Ten Thousand Five Hundred ThirtySix Paise TwentyFive Only
20	Filling foundation and plinth with sand and wel watered &rammedetc . Complete including cost of sand .	5.99	CUM	385.95	2311.84	Rupees Two Thousand Three Hundred Eleven Paise EightyFour Only
21	Cement Concrete (1:3:6) by using 4cm. Size B.H.G. metal including cost, conveyance etc.	5.99	CUM	4118.87	24672.03	Rupees TwentyFour Thousand Six Hundred SeventyTwo Paise Three Only
22	R.R. stone masonry with C.M. (1:6) with all cost , conveyance, etc. complete.	26.54	CUM	3341.49	88683.14	Rupees EightyEight Thousand Six Hundred EightyThree Paise Fourteen Only
23	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete.	2.36	CUM	5022.13	11852.23	Rupees Eleven Thousand Eight Hundred FiftyTwo Paise TwentyThree Only
24	Supplying fitting and placing un coated HYSD Bars reinforcement complete as per drawing and Technical specification.overlaps couplings, welded joints, space bars, chairs stay, hangers, annealed steel wires shall not be required for amount	2.83	kg	9210.40	26065.43	Rupees TwentySix Thousand SixtyFive Paise FourtyThree Only
25	C.B Brick masonry in cement mortar (1:6) by using 9" size C.B.Bricks including all cost, conveyance etc. complete.	12.84	CUM	4023.04	51655.83	Rupees FiftyOne Thousand Six Hundred FiftyFive Paise EightyThree Only
26	12mm thick cement plaster (1:6) for out side plaster.	64.64	SQM	142.29	9197.63	Rupees Nine Thousand One Hundred NinetySeven Paise SixtyThree Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	AMOUNT WITH OUT TAX	AL AMOUNT IN WORDS
27	16mm thick cement plaster (1:6) for Inside plaster.	64.64	SQM	203.97	13184.62	Rupees Thirteen Thousand One Hundred EightyFour Paise SixtyTwo Only
28	20 mm thick cement plaster (1:6) for stone work. Per 1 Sqm.	16.86	SQM	213.57	3600.79	Rupees Three Thousand Six Hundred Paise SeventyNine Only
29	supply of MS grills	123.00	kg	110.00	13530.00	Rupees Thirteen Thousand Five Hundred Thirty Only
30	Painting two coat with any approved paint over a coat of primer on iron works	2.28	SQM	133.89	305.27	Rupees Three Hundred Five Paise TwentySeven Only
31	Distemping Two coat over a coat of white washing including cost conveyance labour & T&P etc complete.	112.41	SQM	63.37	7123.42	Rupees Seven Thousand One Hundred TwentyThree Paise FourtyTwo Only
Total 843277.98						

I, Sri/smt _____ agree to execute the work as per rate quoted by me i.e _____ excess over/less than/ equal to estimated rate ,

Signature of Contractor

P. S. N.
CDM&PHO Gajapati
2/3/23

M. K. S.
25.2.2023
Junior Engineer
NHM, Gajapati

P. S. N.
28/02/2023
Assistant Engineer
NHM Gajapati