

NO. 451

Dt. 10 .12.2021

QUOTATION CALL NOTICE

Sealed Quotation is invited from the intending reputed and registered Odisha based manufacturers/ Authorized dealers/ Distributor/ EPM rate contract holders/ SSI units having valid licenses for supply of 60 MT capacity fully Electronics Type (Pit less Kind) Weigh bridge at **Sub Market Yard, Garabandha.**

The Quotationer shall have to submit double cover system (Cover-I :- **TECHNICAL BID & Cover-II :- PRICE BID**) and super scribe in the covers separately.

1. The Quotationer has to deposit as EMD of **Rs. 20,000/-** in shape of D.D in favour of RMC Paralakhemundi.
2. The successful Quotationer has to deposit the Security Deposit of **Rs.50,000/-** in shape of D.D in favour of RMC Paralakhemundi within 7 days from the finalization of the Quotation.
3. The Quotationer should quote the rate of machinery inclusive labour and transport & other charges.
4. The Quotationer has to quote the rate of each item per unit exclusive tax separately.
5. The Quotationer should be registered from CT & GST Authority and should furnish GST, PAN and valid license.
6. The suppliers of the machinery/ equipment should provide both theoretical and practical training after commissioning the machinery or at an appropriate stage.
7. Delivery of the equipment/ machineries should be within 15 days of receipt of the purchase order.
8. Late & Delayed Quotation offers will not be considered at all.
9. The Quotationer has to submit valid authorization certificate from the manufacturer/ dealer/ distributor for the item quoted.

Contd. to page No. 2....

10. The Quotationer has to produce proof of successful execution of similar nature of work.
11. The Quotation completed in all respect should reach before to the undersigned by Regd. Post or Speed post on or before 24.12.2021 by 5.00 PM.
12. The Quotation will be opened on 28.12.2021 at 11 AM in the office of the RMC Paralakhemundi in presence of the Quotationer or his authorized representatives.
13. The equipment/ machinery & accessories should be delivered, installed and commissioned at the address specified in the order. Service/ operation/ instruction/ calibration manuals (in English) tool kit must also be supplied along with the machinery and accessories.
14. The bidder has to quote price for single unit only. The name and specification of equipment is hereunder ;

SI.No.	SPECIFICATION												
(i)	<p><u>SUPPLY, INSTALLATION &amp; COMMISSIONING OF 60 MT CAPACITY FULLY ELECTRONICS TYPE (PITLES KIND) WEIGH-BRIDGES ON TURNKEY BASIS</u></p> <p>With following specifications &amp; accessories complete along with all civil &amp; electrical works.</p> <table border="1"> <tr> <td>Capacity</td> <td>9.00 M x 3.00 M size Platform frame should be made of M.S Plate fitted with heavy duty joints/ sections as per IS standard adequately reinforced with transverse beams and suitable non-slip top deck.</td> </tr> <tr> <td>Lease Count (e-factor/ increment)</td> <td>Within 5 Kgs</td> </tr> <tr> <td>Type of load cell</td> <td>Compression Load Cell/ Double ended shear beam load cell.</td> </tr> <tr> <td>Indicator/ Display</td> <td>LED with protection against electromagnetic &amp; Radio frequency interference.</td> </tr> <tr> <td>Computer &amp; Printer</td> <td>HCL Desktop PC Intel Processor, 1GB RAM, 160 GB HDD, DVD Writer, 15" LCD Monitor, Keyboard, Mouse, LAN &amp; USB Parallel connectors. Lazer Jet Printer 2 KVA UPS, 1100 VA C.V.T o reputed make including electrical earthing.</td> </tr> <tr> <td>Security Arrangements</td> <td>Security arrangements must be available with the machine in such a manner that, once the verification by Weights &amp; Measure Deptt., is completed, calibrations to the machine setting can not be disturbed. The machine should have both hardware as well as software locking facility. All the load</td> </tr> </table>	Capacity	9.00 M x 3.00 M size Platform frame should be made of M.S Plate fitted with heavy duty joints/ sections as per IS standard adequately reinforced with transverse beams and suitable non-slip top deck.	Lease Count (e-factor/ increment)	Within 5 Kgs	Type of load cell	Compression Load Cell/ Double ended shear beam load cell.	Indicator/ Display	LED with protection against electromagnetic & Radio frequency interference.	Computer & Printer	HCL Desktop PC Intel Processor, 1GB RAM, 160 GB HDD, DVD Writer, 15" LCD Monitor, Keyboard, Mouse, LAN & USB Parallel connectors. Lazer Jet Printer 2 KVA UPS, 1100 VA C.V.T o reputed make including electrical earthing.	Security Arrangements	Security arrangements must be available with the machine in such a manner that, once the verification by Weights & Measure Deptt., is completed, calibrations to the machine setting can not be disturbed. The machine should have both hardware as well as software locking facility. All the load
Capacity	9.00 M x 3.00 M size Platform frame should be made of M.S Plate fitted with heavy duty joints/ sections as per IS standard adequately reinforced with transverse beams and suitable non-slip top deck.												
Lease Count (e-factor/ increment)	Within 5 Kgs												
Type of load cell	Compression Load Cell/ Double ended shear beam load cell.												
Indicator/ Display	LED with protection against electromagnetic & Radio frequency interference.												
Computer & Printer	HCL Desktop PC Intel Processor, 1GB RAM, 160 GB HDD, DVD Writer, 15" LCD Monitor, Keyboard, Mouse, LAN & USB Parallel connectors. Lazer Jet Printer 2 KVA UPS, 1100 VA C.V.T o reputed make including electrical earthing.												
Security Arrangements	Security arrangements must be available with the machine in such a manner that, once the verification by Weights & Measure Deptt., is completed, calibrations to the machine setting can not be disturbed. The machine should have both hardware as well as software locking facility. All the load												

	cells provided should have maintenance free Surge Protection Device. The machine should have provision for auto resetting & weather proof arrangements.
Civil works	Civil works including construction of Scale Room of RCC roofed pucca building of size (10ft x 12ft) & RCC foundation for loading platform complete in all respects (excluding Electric service line connections & approach roads) with glass fitting of windows.
Electrical works	Electrical works required for internal electrification of scale room, weigh bridge/ platform, computerization etc, complete in all respects as per the necessity & requirements for the weighbridge on turn-key basis (excluding electric service line connections)

16. The tender shall reach before the Secretary, RMC Paralakhemundi, Station Road, Hatapada, Paralakhemundi, Gajapati Pin. 761201 by Regd. Post./ Speed post on or before 24.12.2021.

17. The authority reserve all the right to reject all or any of the Tender without assigning any reason thereof.

18. Any non-fulfillment of the above noted terms will make the bid invalid.

The undersigned / purchase committee reserves the rights to negotiate with all or any tender in part or full after sealed tenders are opened in the interest of Govt. and beneficiaries. The Collector-cum-Chairman also reserve the right to cancel/ modify or reject any or all the tender without assigning any reason thereof.

For detail terms and condition available in the web site [www.gajapati.nic.in](http://www.gajapati.nic.in).

  
Collector-cum-Chairman  
Regulated Market Committee  
Paralakhemundi, Gajapati.

Copy to –

- 1) Office notice board of R.M.C., Paralakhemundi
- 2) All the district level officers to display this notice in their office notice board.
- 3) Copy to the DIO, NIC, Gajapati, Paralakhemundi with a request to upload this notice in the district portal ([www.Gajapati.nic.in](http://www.Gajapati.nic.in)).
- 4) Copy submitted to the Collector, Gajapati for favour of kind information and necessary action.
- 5) Copy submitted to the Director Agril., Marketing-cum-Member Secretary, OSAM Board, Shubaneswar for favour of kind information and necessary action.

  
Collector-cum-Chairman  
Regulated Market Committee  
Paralakhemundi, Gajapati.

**RATES & SPECIFICATIONS FOR SUPPLY, INSTALLATION & COMMISSIONING OF 60 MT CAPACITY FULLY ELECTRONICS TYPE (PITLES KIND) WEIGH BRIDGES ON TURNKEY BASIS AT GARABANDHA MARKET YARD UNDER RMC, PARALAKHEMUNDI**

Sl.No.	SPECIFICATION
(i)	<p><u>SUPPLY, INSTALLATION &amp; COMMISSIONING OF 60 MT CAPACITY FULLY ELECTRONICS TYPE (PITLES KIND) WEIGH-BRIDGES ON TURNKEY BASIS</u></p> <p>With following specifications &amp; accessories complete along with all civil &amp; electrical works.</p> <p>Capacity 9.00 M x 3.00 M size Platform frame should be made of M.S Plate fitted with heavy duty joints/ sections as per IS standard adequately reinforced with transverse beams and suitable non-slip top deck.</p> <p>Lease Count (e-factor/ increment) Within 5 Kgs</p> <p>Type of load cell Compression Load Cell/ Double ended shear beam load cell.</p> <p>Indicator/ Display LED with protection against electromagnetic &amp; Radio frequency interference.</p> <p>Computer &amp; Printer HCL Desktop PC Intel Processor, IGB RAM, 160 GB HDD, DVD Writer, 15" LCD Monitor, Keyboard, Mouse, LAN &amp; USB Parallel connectors. Lazer Jet Printer 2 KVA UPS, 1100 VA C.V.T o reputed make including electrical earthing.</p> <p>Security Arrangements Security arrangements must be available with the machine in such a manner that, once the verification by Weights &amp; Measure Deptt., is completed, calibrations to the machine setting can not be disturbed. The machine should have both hardware as well as software locking facility. All the load cells provided should have maintenance free Surge Protection Device. The machine should have provision for auto resetting &amp; weather proof arrangements.</p> <p>Civil works Civil works including construction of Scale Room of RCC roofed pucca building of size (10ft x 12ft) &amp; RCC fooundation for loading platform complete in all respects (excluding Electric service line connections &amp; approach roads) with glass fitting of windows.</p> <p>Electrical works Electrical works required for internal electrification of scale room, weigh bridge/ platform, computerization etc, complete in all respects as per the necessity &amp; requirements for the weighbridge on turn-key basis (excluding electric service line connections)</p>

L. Rosha bely

Secretary  
Regulated Market Committee  
BARALAKHEMUNDI

## ANNEXURE – B

### DETAILED TERMS AND & CONDITIONS

1. The Rates quoted by you should include transportation, packing and forwarding charges, commissioning civil and electrical works, insurance and local costs incidental to delivery and installation charges, but should exclude taxes and duties i.e. the taxes and duties to be mentioned separately.
2. The farm/ supplier must enclose upto date GST clearance certificate and Xerox copy of PAN card. The Quotation will be accepted by the undersigned on 24.12.2021 which shall be opened on 28.12.2021 at 11AM in the presence of the supplier/ farm or their authorized representative. The undersigned has all rights to cancel all quotation/ tender without assigning any reason thereof.
3. The rate quoted by the firms remain valid for a period of one year. The validity of rates can also be extended if agreed to by the Supplier.
4. Delivery/ installation/ commissioning of Weigh bridges shall be made within 1 (one) month time for Weigh bridge failing which, penalty/ liquidated Damages as per shall be imposed.
5. Maximum uptime, downtime & response time as signed by the Supplier in the Bid Document i.e; rectification of any problems that arise shall be done by the Supplier; must also to be maintained by the Supplier failing which penalty will be imposed.
6. It is the responsibility of the Supplier for ensuring satisfactory installation & commissioning of the weigh bridge in the Market Yard of R.M.C, Paralakhemundi etc, failing which final acceptance certificate shall not be issued to the firm. The civil works such as scale room and RCC foundation shall be carried out according to the drawings submitted by the suppliers along with bid documents under the technical supervision of JE/ AE of engineering cell along with the concerned Secretary of RMC. Besides the Supplier will be solely responsible for the structural stability of weigh bridge foundation during the warrantee and AMC period.
7. The Supplier should supply the items in required quantities for which the RMC should mention details of 'Delivery Schedule' in a tabular form including the addresses of the consignee.
8. Training : All necessary exhaustive training programmes to the users (R.M.C) on proper maintenance, repair, over-hauling & operation for all the equipments supplied shall be arranged by the respective Suppliers in Odisha for sufficient number of days on free of cost.
9. Warrantee/ Guarantee : Comprehensive warranty for all the items shall remain valid for 2 (two) years in case of weigh bridges after the same have been delivered, commissioned and accepted at the final destination to be indicated in the agreement/ contact/ purchase orders manufacture's Guarantee/ Warranty Certificate should also be submitted in the R.M.C for the items supplied by the supplier along with the materials.
10. Terms & Services for Annual Maintenance Contact (A.M.C) for a period of 4 (four) years after the expiry of guarantee/ warranty period by the Supplier/ Manufacturer must be strictly adhered.

L. Ro Lakshy

Secretary

Regulated Market Committee  
BARALAKHEMUNDI