

**BILL OF QUANTITY**

Name of the work

CONSTRUCTION OF DAY CARE SUB CENTRE-CUM-  
HEALTH &WELLNESS CENTRE AT TUMBA UNDER  
RAYAGADA BLOCK FOR THE YEAR 2021-22 SANCTIONED  
IN PM-ABHIM

Estimated Cost

49,70,000.00

Amount Put to Tender

4172036.00

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
1	Excavation for in soil with hydraulic excavator of 0.9cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections and transporting to the embankment locations with all lifts & leads up to 1000m.as per approved Drawing & Technical Specifications and as per Clause - 301 of MoSRT&H Specifications for Road & Bridge works (Latest Revision).	602.18	CUM	42.51	25598.67	Rupees TwentyFive Thousand Five Hundred NinetyEight Paise SixtySeven Only
2	Earth work in all kinds of soil within 50m. Initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm.to 7cm. and laying in layers not exceeding 0.3 m. in depth asper direction of the Engineer-in-charge.	174.64	CUM	219.78	38382.38	Rupees ThirtyEight Thousand Three Hundred EightyTwo Paise ThirtyEight Only
3	Filling foundation and plinth with sand and wel watered &rammedetc . Complete including cost of sand .	83.65	CUM	519.27	43436.94	Rupees FourtyThree Thousand Four Hundred ThirtySix Paise NinetyFour Only
4	Cement Concrete (1:3:6) by using 4cm. Size B.H.G. metal including cost, conveyance etc.	33.98	CUM	4355.30	147993.09	Rupees One Lakh FourtySeven Thousand Nine Hundred NinetyThree Paise Nine Only
5	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete.for footing	14.60	CUM	5261.16	76812.94	Rupees SeventySix Thousand Eight Hundred Twelve Paise NinetyFour Only
6	R.R. stone masonry with C.M. (1:6 ) with all cost , conveyance, etc. complete.	74.38	CUM	3448.19	256476.37	Rupees Two Lakh FiftySix Thousand Four Hundred SeventySix Paise ThirtySeven Only
7	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. Plinth beam complete.	8.67	CUM	5527.57	47924.03	Rupees FourtySeven Thousand Nine Hundred TwentyFour Paise Three Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
8	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. Column	6.36	CUM	11249.86	71549.11	Rupees SeventyOne Thousand Five Hundred FourtyNine Paise Eleven Only
9	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. Lintel	2.80	CUM	8974.68	25129.10	Rupees TwentyFive Thousand One Hundred TwentyNine Paise Ten Only
10	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. Chajja	32.70	SQM	813.70	26607.99	Rupees TwentySix Thousand Six Hundred Seven Paise NinetyNine Only
11	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. Roof beam	5.24	CUM	11249.86	58949.27	Rupees FiftyEight Thousand Nine Hundred FourtyNine Paise TwentySeven Only
12	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. Roof slab	12.89	CUM	9600.05	123744.64	Rupees One Lakh TwentyThree Thousand Seven Hundred FourtyFour Paise SixtyFour Only
13	Supplying fitting and placing un coated HYSD Bars reinforcement complete as per drawing and Technical specification. overlaps couplings, welded joints, space bars, chairs stay, hangers, annealed steel wires shall not be measured for payment.	63.01	QNTL	8804.70	554784.15	Rupees Five Lakh FiftyFour Thousand Seven Hundred EightyFour Paise Fifteen Only
14	Fly ash brick masonry in cement mortar (1:6) by using 9" size fly ash bricks including all cost, conveyance etc. complete.	56.76	CUM	4524.52	256811.76	Rupees Two Lakh FiftySix Thousand Eight Hundred Eleven Paise SeventySix Only
15	12mm thick cement plaster (1:6) for out side plaster.	327.42	SQM	147.00	48130.74	Rupees FourtyEight Thousand One Hundred Thirty Paise SeventyFour Only
16	16mm thick cement plaster (1:6) for Inside plaster.	327.42	SQM	209.63	68637.05	Rupees SixtyEight Thousand Six Hundred ThirtySeven Paise Five Only
17	20 mm thick cement plaster (1:6) for stone work. Per 1 Sqm.	140.19	SQM	220.66	30934.33	Rupees Thirty Thousand Nine Hundred ThirtyFour Paise ThirtyThree Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
18	Providing fitting & fixing of vetrified tiles in floor including cost, conveyance etc complete.(PLAIN IVORY) over 20mm thick cement mortar (1:4) complete.	82.75	SQM	860.56	71211.34	Rupees SeventyOne Thousand Two Hundred Eleven Paise ThirtyFour Only
19	Providing and fixing Ceramic tiles in dados, skirtings and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles as directed by the Engineer-in-charge.	47.57	SQM	731.50	34797.46	Rupees ThirtyFour Thousand Seven Hundred NinetySeven Paise FourtySix Only
20	Providing and fixing Ceramic tiles in floors, treads or steps and landing on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slury mixed with pigment to match the shades of the tiles .	7.62	SQM	764.53	5825.72	Rupees Five Thousand Eight Hundred TwentyFive Paise SeventyTwo Only
21	supply of MS grills	463.580	KG	83.00	38477.14	Rupees ThirtyEight Thousand Four Hundred SeventySeven Paise Fourteen Only
22	supply of MS shutter Door	1094.00	KG	87.00	95178.00	Rupees NinetyFive Thousand One Hundred SeventyEight Only
23	Painting two coat with any approved paint over a coat of primer on iron works	73.94	SQM	140.34	10376.74	Rupees Ten Thousand Three Hundred SeventySix Paise SeventyFour Only
24	Distempering Two coat over a coat of white washing including cost conveyance labour & T&P etc complete.	466.54	SQM	66.28	30922.27	Rupees Thirty Thousand Nine Hundred TwentyTwo Paise TwentySeven Only
25	Painting two coats with weather seal paint over a coat of primer including cost, conveyance all materilas, labour and T & P etc complete.	134.67	SQM	135.78	18285.49	Rupees Eighteen Thousand Two Hundred EightyFive Paise FourtyNine Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
26	Supplying fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90 Mtr. Center to Center and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials labour, T & P etc required for the work complete in all respect as directed by the Engineer in charge.	60.65	kg	335.29	20335.34	Rupees Twenty Thousand Three Hundred ThirtyFive Paise ThirtyFour Only
	1ST FLOOR					
27	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 1st floor column	4.32	CUM	14029.68	60608.22	Rupees Sixty Thousand Six Hundred Eight Paise TwentyTwo Only
28	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 1st floor LINTEL	2.34	CUM	9456.05	22127.16	Rupees TwentyTwo Thousand One Hundred TwentySeven Paise Sixteen Only
29	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 1st floor Chajja	28.17	SQM	878.43	24745.37	Rupees TwentyFour Thousand Seven Hundred FourtyFive Paise ThirtySeven Only
30	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 1st floor Roof beam	4.38	CUM	14029.68	61450.00	Rupees SixtyOne Thousand Four Hundred Fifty Only
31	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 1st floor Roof slab	10.51	CUM	10225.11	107465.91	Rupees One Lakh Seven Thousand Four Hundred SixtyFive Paise NinetyOne Only
32	Supplying fitting and placing un coated HYSD Bars reinforcement complete as per drawing and Technical specification.overlaps couplings, welded joints, space bars, chairs stay, hangers, annealed steel wires shall not be measured for payment.For 1st floor	32.20	QNTL	8828.45	284276.09	Rupees Two Lakh EightyFour Thousand Two Hundred SeventySix Paise Nine Only
33	Fly ash brick masonary in cement mortar (1:6) by using 9" size fly ash bricks including all cost, conveyance etc. complete.	34.68	CUM	4790.98	166151.19	Rupees One Lakh SixtySix Thousand One Hundred FiftyOne Paise Nineteen Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
34	12mm thick cement plaster (1:6) for out side plaster. For 1st floor	218.99	SQM	150.30	32914.20	Rupees ThirtyTwo Thousand Nine Hundred Fourteen Paise Twenty Only
35	16mm thick cement plaster (1:6) for Inside plaster. For 1st floor	218.99	SQM	217.83	47702.59	Rupees FourtySeven Thousand Seven Hundred Two Paise FiftyNine Only
36	Providing fitting & fixing of vetrified tiles in floor including cost, conveyance etc complete.(PLAIN IVORY) over 20mm thick cement mortar (1:4) complete.	74.05	sQM	869.46	64383.51	Rupees SixtyFour Thousand Three Hundred EightyThree Paise FiftyOne Only
37	Providing and fixing Ceramic tiles in dados, skirtings and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles as directed by the Engineer-in-charge. For 1st Floor	35.24	sQM	746.24	26297.50	Rupees TwentySix Thousand Two Hundred NinetySeven Paise Fifty Only
38	Providing and fixing Ceramic tiles in floors, treads or steps and landing on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles . For 1st Floor	7.64	sQM	774.32	5915.80	Rupees Five Thousand Nine Hundred Fifteen Paise Eighty Only
39	supply of MS grills For 1st floor	376.00	KG	83.00	31208.00	Rupees ThirtyOne Thousand Two Hundred Eight Only
40	supply of MS shutter For 1st floor	1012.00	KG	87.00	88044.00	Rupees EightyEight Thousand FourtyFour Only
41	Painting two coat with any approved paint over a coat of primer on iron works For 1st floor	67.40	SQM	143.81	9692.79	Rupees Nine Thousand Six Hundred NinetyTwo Paise SeventyNine Only
42	Distempering Two coat over a coat of white washing including cost conveyance labour & T&P etc complete. For 1st floor	535.60	SQM	67.80	36313.68	Rupees ThirtySix Thousand Three Hundred Thirteen Paise SixtyEight Only
43	Painting two coats with weather seal paint over a coat of primer including cost, conveyance all materilas, labour and T & P etc complete.	134.67	sQM	140.73	18952.11	Rupees Eighteen Thousand Nine Hundred FiftyTwo Paise Eleven Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
44	Supplying fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90 Mtr. Center to Center and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials labour, T & P etc required for the work complete in all respect as directed by the Engineer in charge.	60.62	KG	335.29	20325.28	Rupees Twenty Thousand Three Hundred TwentyFive Paise TwentyEight Only
Head Room( 2nd Floor)						
45	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 2nd floor column	0.96	CUM	15516.63	14895.96	Rupees Fourteen Thousand Eight Hundred NinetyFive Paise NinetySix Only
46	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 2nd floor LINTEL	0.42	CUM	10029.58	4212.42	Rupees Four Thousand Two Hundred Twelve Paise FourtyTwo Only
47	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 2nd floor Chajja	1.86	SQM	955.84	1777.86	Rupees One Thousand Seven Hundred SeventySeven Paise EightySix Only
48	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 2nd floor Roof beam	1.09	CUM	15516.63	16913.13	Rupees Sixteen Thousand Nine Hundred Thirteen Paise Thirteen Only
49	R.C.C. work of M 20 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete. For 2 nd floor Roof slab	1.94	CUM	10970.92	21283.58	Rupees TwentyOne Thousand Two Hundred EightyThree Paise FiftyEight Only
50	Supplying fitting and placing un coated HYSD Bars reinforcement complete as per drawing and Technical specification.overlaps couplings, welded joints, space bars, chairs stay, hangers, annealed steel wires shall not be measured for payment.For 2nd floor	6.27	QNTL	8853.40	55510.82	Rupees FiftyFive Thousand Five Hundred Ten Paise EightyTwo Only
51	Fly ash brick masonry in cement mortar (1:6) by using 9" size fly ash bricks including all cost, conveyance etc. complete. For 2nd floor	11.23	CUM	5097.40	57243.80	Rupees FiftySeven Thousand Two Hundred FourtyThree Paise Eighty Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
52	12mm thick cement plaster (1:6) for out side plaster. For 2nd floor	58.63	SQM	150.30	8812.09	Rupees Eight Thousand Eight Hundred Twelve Paise Nine Only
53	16mm thick cement plaster (1:6) for Inside plaster. For 2nd floor	58.63	SQM	226.43	13275.59	Rupees Thirteen Thousand Two Hundred SeventyFive Paise FiftyNine Only
54	supply of MS shutter For 2nd floor	86.00	KG	87.00	7482.00	Rupees Seven Thousand Four Hundred EightyTwo Only
55	Painting two coat with any approved paint over a coat of primer on iron works For 2nd floor	5.12	SQM	147.40	754.69	Rupees Seven Hundred FiftyFour Paise SixtyNine Only
56	Distemping Two coat over a coat of white washing including cost conveyance labour & T&P etc complete. For 2nd floor	84.22	SQM	67.80	5710.12	Rupees Five Thousand Seven Hundred Ten Paise Twelve Only
57	Painting two coats with weather seal paint over a coat of primer including cost, conveyance all materilas, labour and T & P etc complete. For 2nd floor	105.86	SQM	145.92	15447.09	Rupees Fifteen Thousand Four Hundred FourtySeven Paise Nine Only
	PH Work					
58	Earthwork in all kinds of soil in excavation of foundation trenches within 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc all complete as per direction of the E.I.C.					
a	Initial lift upto 1.5 mtr	13.487	Cum	219.78	2964.17	Rupees Two Thousand Nine Hundred SixtyFour Paise Seventeen Only
b	From 1.5 mtr to 3.0 mtr depth	6.294	Cum	217.16	1366.81	Rupees One Thousand Three Hundred SixtySix Paise EightyOne Only
59	Supplying all materials, labour, T&P and filling in foundation and plinth with river sand well watered and rammed including conveyance of all materials to work site, payment of royalty, taxes etc all complete as per the direction of the E.I.C.	1.348	Cum	519.27	699.98	Rupees Six Hundred NinetyNine Paise NinetyEight Only
60	Supplying all materials, labour, T&P and providing cement concrete (1:3:6) with 40mm H.G metal including watering, curing and conveyance of all materials to site payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	1.348	Cum	4355.30	5870.94	Rupees Five Thousand Eight Hundred Seventy Paise NinetyFour Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
61	Supplying all materials, labour, T&P and providing plain cement concrete (1:1.5:3) with 12mm size H.G chips including watering, curing and conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	1.047	Cum	6986.65	7315.02	Rupees Seven Thousand Three Hundred Fifteen Paise Two Only
62	Supplying all materials,labour, T&P and providing Brick work with K.B.Brick having crushing strength not less than 75 Kg/CM <sup>2</sup> with dimensional tolerance of +/- 8% in C.M including watering, curring,					
a	In Foundation and Plinth in C:M (1:4)	5.434	Cum	4181.86	22724.23	Rupees TwentyTwo Thousand Seven
b	In Foundation and Plinth in C:M (1:6)	0.096	Cum	4257.01	408.67	Rupees Four Hundred Eight Paise SixtySeven
63	Supplying all materials, labour, T&P and providing cement plaster on brick/stone work including watering,curring and conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	21.191	SQM	161.50	3422.35	Rupees Three Thousand Four Hundred TwentyTwo Paise ThirtyFive Only
64	Supplying all materials, labour, T&P and providing cement punning on plastered surface including watering,curring and conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	20.231	SQM	31.80	643.35	Rupees Six Hundred FourtyThree Paise ThirtyFive Only
65	Supplying all materials, labour, T&P and providing rigid and smooth centering and shuttering for RCC work including false work and dismantling them after casting including conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	5.161	SQM	437.10	2255.87	Rupees Two Thousand Two Hundred FiftyFive Paise EightySeven Only
66	Supplying all materials, labour, T&P and providing M.S.reinforcements for RCC work including cutting, bending, binding, straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	0.550	Qntl	5561.10	3058.61	Rupees Three Thousand FiftyEight Paise SixtyOne Only
67	Supplying all materials, labour, T&P and providing Reinforced cement concrete (1:1.5:3) with 12mm size H.G chips including watering, curing and conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	0.750	Cum	6659.70	4994.78	Rupees Four Thousand Nine Hundred NinetyFour Paise SeventyEight Only
68	Supplying all materials, labour, T&P and making M.S. Step Iron in 8mm Dia M.S Steel bars and fixing into walls of Manhole/ Septic Tanks duly embedded in C.C(1:2:4) etc all complete as per P.H specification and direction of the E.I.C.	5.000	Each	116.80	584.00	Rupees Five Hundred EightyFour Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
69	Supplying all materials, labour, T&P and providing 50mm thick pre-cast R.C.C. baffle wall in R.C.C.(1:1.5:3) including reinforcement cage using 12mm size HG chips fitted and fixed in position, finished smooth etc. complete including cutting	0.787	SQM	698.50	549.72	Rupees Five Hundred FourtyNine Paise SeventyTwo Only
70	Supplying all materials, labour, T&P and providing 160mm dia P.V.C Tee inside the septic tank including cutting holes and duly embedded in P.C.C(1:1.5:3) using 12mm size HG chips fitted and fixed in position and making good the damages etc all	2.000	Each	584.00	1168.00	Rupees One Thousand One Hundred SixtyEight Only
71	Supplying all materials, labour, T&P and providing 12mm thick cement flush pointing in C:M (1:3) to Brick Masonry works including watering curring and conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C.	22.257	SQM	142.60	3173.85	Rupees Three Thousand One Hundred SeventyThree Paise EightyFive Only
72	Supplying all materials, labour, T&P and filling Foundation and Plinth with excavated earth including watering, ramming etc all complete as per direction of the E.I.C.	4.700	Cum	114.59	538.57	Rupees Five Hundred ThirtyEight Paise FiftySeven Only
73	Supplying all materials, labour, T&P and fixing wash down water closet(E.W.C) with integral 'S' or 'P' trap with Seat cover to the floor with wooden plug and C.P screw including jointing the trap with soil waste pipe in C.M(1:1) etc all complete as per	4.000	No	2682.80	10731.20	Rupees Ten Thousand Seven Hundred ThirtyOne Paise Twenty Only
74	Supplying all materials, labour T&P and fitting and fixing 10 Ltrs capacity PVC low level flushing cistern(Hindware, Parryware, Cera) with a pair of C.I. or M.S.brackets complete with fittings such as subsoil arrangement, 15mm	4.000	Each	1488.10	5952.40	Rupees Five Thousand Nine Hundred FiftyTwo Paise Fourty Only
75	Supplying all materials, labour T&P and fixing <b>wash basins</b> with hole for pillar taps with C.I./M.S brackets painted white including holes in walls and making good the damages etc. all complete as per P.H specification and direction of E.I.C.- <b>550mm x 400mm WHB with all Fittings with C.P. Waste, &amp; Connection Pipe. (Neycer/Cerra/ Parry ware/ Hindware)</b>	4.000	No	2671.90	10687.60	Rupees Ten Thousand Six Hundred EightySeven Paise Sixty Only
a	32mm Dia Bottle Trap (cat. No F8060403)	4.000	No	2045.00	8180.00	Rupees Eight Thousand One Hundred Eighty Only
76	Supplying all materials, labour T&P and fixing mirror of superior glass mounted on 6mm thick plywood sheet and fixed to wooden plugs with C.P screws and washers complete as per P.H specification and direction of E.I.C.- <b>600mm x 450mm B.E. Mirror (fixed type)</b>	4.000	Nos	705.70	2822.80	Rupees Two Thousand Eight Hundred TwentyTwo Paise Eighty Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
77	Supplying all materials, labour T&P and fixing standard size <b>C.P. towel rail / ring</b> complete with c.p. brass brackets fixed to wooden plugs with c.p screws as per P.H specification and direction of E.I.C.- <b>25 mm</b>	4.000	Nos	1009.10	4036.40	Rupees Four Thousand ThirtySix Paise Fourty Only
a	C.P. Towel Ring (St.)	4.000	Nos	427.20	1708.80	Rupees One Thousand Seven Hundred Eight Paise Eighty Only
78	Supplying all materials, labour T&P and fixing standard size <b>C.P. soap holder</b> complete with c.p brass brackets fixed to wooden plugs with cp screws as per PH specification and direction of E.I.C.- <b>C.P.Soap Holder.</b>	4.000	Nos	271.10	1084.40	Rupees One Thousand EightyFour Paise Fourty Only
79	Supplying all materials, labour T&P and <b>cutting holes</b> through brick/stone masonry walls for taking PVC pipes and fittings including making good the damages etc. all complete as per P.H. specification and direction of E.I.C. - <b>250 mm thick wall</b>	10.000	Nos	178.50	1785.00	Rupees One Thousand Seven Hundred EightyFive Only
a	375 mm thick wall	10.000	Nos	227.00	2270.00	Rupees Two Thousand Two Hundred Seventy Only
80	Supplying all materials, labour, T&P and providing and fixing to wall or ceiling and floor PVC Pipes conforming to ASTM-D-1785/89(sch-40/80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor testing all complete as per specification and direction of E.I.C.- <b>25 mm dia PVC [ASTM] Pipe [Internal]</b>	40.000	Mtr	195.50	7820.00	Rupees Seven Thousand Eight Hundred Twenty Only
81	Supplying all materials, labour, T&P and cutting holes through brick/stone masonry works including making good the damages in c.m. (1:4) for taking P.V.C. pipes & fittings etc. all complete as per P.H. specification and direction of E.I.C.	10.000	Nos	49.00	490.00	Rupees Four Hundred Ninety Only
82	Supplying all materials, labour, T&P and cutting grooves in pucca floors and walls for taking G.I./P.V.C. pipes and making good the damages as per direction of the E.I.C.	20.000	Mtr	167.50	3350.00	Rupees Three Thousand Three Hundred Fifty Only
83	Supplying all materials, labour, T&P and Fitting and Fixing of Rotational moulded polythene cylindrical vertical water storage tank conforming to 15701/1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra	1.000	Each	8913.90	8913.90	Rupees Eight Thousand Nine Hundred Thirteen Paise Ninety Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
84	Supplying all materials, labour, T&P and construction of masonry staging with providing 1st class K.B. Brick work in C.M.(1:6) of 0.46mtr height in staging, 12 mm cement plaster in C.M (1:6), R.C.C. Beam of 0.25mx0.30mx2.60m & roof slab of 1.40mx1.40m in C.C (1:1.5:3) using 12mm size H.G.Chips including centering, shuttering, bending and binding of rod etc watering, curing, conveyance of all materials to work site, payment of royalty, taxes etc all complete as per P.H specification and direction of the E.I.C. 1000 lits capacity on the roof of ground floor	1.000	Each	11239.20	11239.20	Rupees Eleven Thousand Two Hundred ThirtyNine Paise Twenty Only
85	Supplying all materials, labour, T&P and constructing Inspection Chamber of the following sizes with cement concrete (1:3:6) using 40 mm size HG metal on bed, 1st class KB Brick work in CM (1:6) moulding and shaping the channel inside and benching with C:C (1:1.5:3) using 12 mm size H.G chips, 12 mm thick cement plaster (1:3) with punning to inside, cement flush pointing (1:3) to outside, RCC cover slab in C.C(1:1.5:3) using 12 mm size H.G chips with RCC man hole cover, earth work excavation in all kinds of soil and refilling the cavity around the chamber including watering, curing, conveyance of all materials to worksite, payment of royalty, taxes etc. all complete as per approved specification and direction of E.I.C					
	Inside size 760mm x 760mm x 460mm	2.000	Each	7261.70	14523.40	Rupees Fourteen Thousand Five Hundred TwentyThree Paise Fourty Only
86	Supplying all materials, labour, T&P and constructing Gully Trap chamber of the following inside size with 8 cm thick precast cover slab in CC (1:2:4) mix using 12 mm size H.G chips, foundation concrete (1:4:8) using 40 mm size HG metal on bed and	4.000	Each	1465.90	5863.60	Rupees Five Thousand Eight Hundred SixtyThree Paise Sixty Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
87	Factory made FRP(alternately called GRP) door frame of size 75mmx100mm fabricated using E-glass Chopped Strand Mat (CSM) U.V stabilised Inophthalic Gelcoat and impregnated with Inophthalic resin. The thickness of the GRP skins shall not be less than 2.00mm. The door frame consist of four segments which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screw. The GRP frame shall be provided with wooden reinforcement on six locations for high screw holding capacity for for fixing metallic hold fast and shall be consolidated by filling with medium density foam/plaster of paris with fibre reinforcement, Six numbers of 260mm x 25mm x 5mm size 'S' shaped M.S flat hold fast shall be provided with the frame. The material and process for manufacturing the door frames shall conform to RV-TIFAC composites Design Centre's standards and specifications. The finish of door frame will be plain colour white/ Ivory/ Beige/ Light grey/ Golden brown/Mahogany/ Teak wood/sand stone/Champagne/Pastel blue or any other colour using high quality pigments complete in all respect as per specification and direction of the E.I.C	19.800	Mtrs	551.70	10923.66	Rupees Ten Thousand Nine Hundred TwentyThree Paise SixtySix Only
88	Factory made single leaf rigid FRP(alternately called GRP) sandwich composite door shutter of 32mm thick laminated with two GRP skins with wood grain finish fabricated using UV-stabilised Inophthalic Gelcoat and one layer of 450 gsm	5.600	Sqmt	3181.10	17814.16	Rupees Seventeen Thousand Eight Hundred Fourteen Paise Sixteen Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
89	Supplying all materials, labour, T&P and constructing soakway pit of the following size with dry brick walling from bottom upto invert of inlet pipe and 1st class KB brick work in CM (1:6) for the remaining height at top, 12mm thick Cement Plaster (1:4) inside and outside over masonry brick work, gravel packing in the rear of well steining, RCC cover slab in CC (1:1.5:3) using 12mm HG chips, fitted with iron lifting handles including earthwork in open well excavation in all kinds of soil and refilling of cavity around the pit & painting the iron works, watering, curing, conveyance of all materials to work site, payment of royalty, taxes etc all complete as per approved specification and direction of the E.I.C. Soak way Pit (0.90 m dia x 2.00m Ring Soak Way Pit)	4.000	Each	3305.00	13220.00	Rupees Thirteen Thousand Two Hundred Twenty Only
90	Supplying all materials, labour, T&P and fitting and fixing U-PVC SWR soil waste ventilating pipes and fittings of the following outside diameter conforming to ISI No 13592/1992 to walls with nails, bobbins and wooden plugs including jointing with supply of approved rubber lubricant by non-heat application method/as per manufacturer's specification, testing etc all complete as per P.H specification and direction of the E.I.C. 110mm diameter U-PVC SWR pipes	30.000	Mtr	318.80	9564.00	Rupees Nine Thousand Five Hundred SixtyFour Only
a	110mm U-PVC SWR P-trap	4.000	Each	299.70	1198.80	Rupees One Thousand One Hundred NinetyEight Paise Eighty Only
b	110mm U-PVC SWR single junction door	4.000	Each	296.70	1186.80	Rupees One Thousand One Hundred EightySix Paise Eighty Only
c	110mm U-PVC SWR door bend	4.000	Each	204.70	818.80	Rupees Eight Hundred Eighteen Paise Eighty Only
d	110mm U-PVC SWR plain bend	4.000	Each	147.00	588.00	Rupees Five Hundred EightyEight Only
e	110mm U-PVC SWR vent cowl	4.000	Each	77.30	309.20	Rupees Three Hundred Nine Paise Twenty Only
f	110mm U-PVC SWR Offset	4.000	Each	180.50	722.00	Rupees Seven Hundred TwentyTwo Only
g	125 mm dia C.P Grating	10.000	Each	70.00	700.00	Rupees Seven Hundred Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
91	supplying all materials, labour, T&P and cutting grooves in pucca Floors, and walls for taking G.I/PVC pipes and fittings and repairing the holes after insertion of pipes etc with C.C (1:3:6) including finishing with 12mm C.P (1:3) complete so as to make it leak proof etc. all complete as per P.H. specification and direction of E.I.C.	20.000	Mtr	179.50	3590.00	Rupees Three Thousand Five Hundred Ninety Only
92	Supplying all materials, labour, T&P and providing and fixing to wall or ceiling or floor G.I. pipes and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling, and floor, testing all complete as per specification and the					
a	15mm dia PVC pipes ( Internal CPVC )	10.000	Mtr	185.20	1852.00	Rupees One Thousand Eight Hundred FiftyTwo Only
b	25mm dia PVC pipes ( CPVC PIPES )	20.000	Mtr	193.50	3870.00	Rupees Three Thousand Eight Hundred Seventy Only
c	32mm HDPE Pipes	50.000	Mtr	78.10	3905.00	Rupees Three Thousand Nine Hundred Five Only
93	Supplying all materials, labour, T&P and fitting and fixing Brass/CP fittings(Jaquar) of the following nominal bore with supply of all jointing materials etc. all complete as per specification and the direction of the E.I.C. (jaquar ).					
a	15mm dia CP Bib Cock	2.000	Each	1038.60	2077.20	Rupees Two Thousand SeventySeven Paise Twenty Only
b	15mm dia CP Concealed Stop Cock	2.000	Each	1546.10	3092.20	Rupees Three Thousand NinetyTwo Paise Twenty Only
c	15 mm dia CP Angle cock	4.000	Each	881.70	3526.80	Rupees Three Thousand Five Hundred TwentySix Paise Eighty Only
d	15mm dia C.P. Two Way Bib cok [Jaquar]	2.000	Each	1136.80	2273.60	Rupees Two Thousand Two Hundred SeventyThree Paise Sixty Only
e	15mm dia CP Pillar Cock	2.000	Each	1443.30	2886.60	Rupees Two Thousand Eight Hundred EightySix Paise Sixty Only
f	15mm dia CP nipple	10.000	Each	58.70	587.00	Rupees Five Hundred EightySeven Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
g	15mm dia CP Flange	10.000	Each	39.90	399.00	Rupees Three Hundred NinetyNine Only
h	25mm Full Way Valve	2.000	Each	1057.50	2115.00	Rupees Two Thousand One Hundred Fifteen Only
i	15 mm x 150mm dia C.P Shower with arm	2.000	Each	495.00	990.00	Rupees Nine Hundred Ninety Only
94	Supplying all materials, labour, T&P and laying in trenches U-PVC SWR/4kg/cm2 soil waste ventilating pipes and fittings of the following outside diameter conforming to ISI No 13592/1992 including jointing with supply of approved rubber lubricant by non-heat application method/as per manufacturer's specification, testing, earthwork in excavation in all kinds of soil and providing bed concrete in P:C:C (1:4:8) using 40 mm size metal and haunch top the pipe with refilling of trenches etc all complete as per P.H specification and direction of the E.I.C. 110 mm dia PVC Pipe haunch top	6.000	Mtr	974.70	5848.20	Rupees Five Thousand Eight Hundred FourtyEight Paise Twenty Only
95	Supplying all materials, labour, T&P and laying in trenches U-PVC SWR/4kg/cm2 soil waste ventilating pipes for sewer line of following dia in trenches (to slope or level)and jointing with supply of approved solvent cement by non heat application	6.000	Mtr	1915.50	11493.00	Rupees Eleven Thousand Four Hundred NinetyThree Only
96	Supplying and fitting & fixing of I.S.I make 1.0 H.P single phase Submersible Pump set to give discharge of 3000 ltr/hour at a head of 40 mtr etc all complete as direction of EIC.	1.000	Each	15849.15	15849.15	Rupees Fifteen Thousand Eight Hundred FourtyNine Paise Fifteen Only
97	Supplying all labour, T&P and fitting & fixing of I.S.I make 1.00 H.P single phase Submersible Pump set with commissioning and testing etc all complete as direction of EIC.	1.000	Each	1475.00	1475.00	Rupees One Thousand Four Hundred SeventyFive Only
98	Supplying and fitting & fixing of D.O.L starter for 1.0 H.P single phase Submersible Pump etc all complete as per direction of Engineer-in-charge.	1.000	Each	2809.32	2809.32	Rupees Two Thousand Eight Hundred Nine Paise ThirtyTwo Only
99	Supplying and fitting & fixing of suitable cable and connecting the pump and starter etc all complete as per direction of Engineer-in-charge.	56.000	mtr	71.70	4015.20	Rupees Four Thousand Fifteen Paise Twenty Only
100	Supplying and fitting & fixing of Plastic rope, M.S well cover, M.S clamp, etc all complete as per direction of Engineer-in-charge.	1.000	Each	1660.00	1660.00	Rupees One Thousand Six Hundred Sixty Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
101	Supplying and fitting & fixing of HDPE pipes and pipe fittings with C.P Nippling and lowering to bore well, making connection to pumpset & testing etc all complete as per specification and the direction of the E.I.C.	120.000	Mtr	119.50	14340.00	Rupees Fourteen Thousand Three Hundred Fourty Only
a	32mm dia HDPE pipes					
102	Labour for drilling a perfectly vertical bore hole at specified dia for a specified depth below ground level through consolidated and unconsolidated rock with down the hole hammer drilling rigs or combination rigs as required to suit the site condition as per the direction of the Engineer-in-charge including use of own rigs with its accessories, tools and plants and consumables etc for lowering of 125 mm dia P.V.C/G.I./MS pipes for housing fitted socket and with or without well screen as per the necessity for soft, medium, hard and boulder formation (G.I/P.V.C/M.S casing pipes if required to prevent collapse of over burden is to be provided by the contractor including lowering and withdrawing after completion of the tubewell)					
a	Drilling of 125mm dia bore :-00 mtr to 40.00 mtr	40.000	mtr	490.00	19600.00	Rupees Nineteen Thousand Six Hundred Only
b	Drilling of 100mm dia bore :-40.01 mtr to 90.00 mtr	30.000	mtr	490.00	14700.00	Rupees Fourteen Thousand Seven Hundred Only
103	Lowering of the following size G.I/P.V.C pipes with or without slotted pipes as per the necessary from ground level upto 30 mtrs depth and fitted and fixed up in perfectly vertical position including cutting and threading pipes and slotted pipe and supplying and fixing all jointing materials, tools and plants complete and keeping the top of the casing pipe threaded including plugging tubewell to prevent entry of foreign materials from above.	13.490				
a	Lowering of 125 mm dia PVC pipes :- 00mtr to 30.00 mtr	15.000	mtr	122.60	1839.00	Rupees One Thousand Eight Hundred ThirtyNine Only
b	Cost of 125 mm dia PVC pipes :- 00mtr to 30.50 mtr	15.000	mtr	928.32	13924.80	Rupees Thirteen Thousand Nine Hundred TwentyFour Paise Eighty Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
104	Cleaning and developing the tube well using their own compressor continuously worked till clean and adequate discharge is obtained from the tubewell including supply and use of all necessary equipments and labour as per the direction of Engineer-in-charge.	1.000	Each	4392.00	4392.00	Rupees Four Thousand Three Hundred NinetyTwo Only
<b>EI Work</b>						
105	Recessed wiring to light and fan points with 1.5 sq.mm. FR PVC insulated single core multistrand copper conductor of ISI marked with 20mm dia non-metallic PVC flexible conduit with 6Amp. 250V Modular switch ISI marked and ceiling rose ISI marked mounted on Metal box having front Modular cover of suitable size, metal box with 1.5sqmm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection (Make of wire Finolex / L & T / Anchor / Havells / V-Guard)					
	a. Group-A	20.000	Point	512.00	10240.00	Rupees Ten Thousand Two Hundred Forty Only
	b. Group-B	22.000	Point	731.00	16082.00	Rupees Sixteen Thousand EightyTwo Only
	c. Group-C	32.000	Point	1006.00	32192.00	Rupees ThirtyTwo Thousand One Hundred NinetyTwo Only
106	Supply and fixing of 6 Amp. Plug with 6 Amp. Switch on existing board (Modular type)	13.000	Each	223.00	2899.00	Rupees Two Thousand Eight Hundred NinetyNine Only
107	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 2 Nos. of 6 Amp. Modular switches and socket connection (make – Anchor / Legrand / Roma)	9.000	Each	877.00	7893.00	Rupees Seven Thousand Eight Hundred NinetyThree Only
108	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 16 Amp. Socket outlet and 16 Amp. Modular switches connection (make – Anchor / Legrand / Roma)	9.000	Each	867.00	7803.00	Rupees Seven Thousand Eight Hundred Three Only
109	S/F of 1 No. of 5 pin 15/16 Amp. Socket, 1 No. of switch and 1 No. of 15/16A top with modular mini MCB, in 6 modular box with cover with connection, painting etc. as required for inverter connection.	2.000	Each	1174.01	2348.02	Rupees Two Thousand Three Hundred FourtyEight Paise Two Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
110	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 03 Nos. of 6 pin 5/6 and 01 No. of 15/16A modular socket outlet and 15/16A modular switch connections etc. as required (multipurpose board)	6.000	Each	1507.94	9047.64	Rupees Nine Thousand FourtySeven Paise SixtyFour Only
111	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic cover for the MCB knobs detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but without MCB / RCCB / Isolator)					
	a. 8 Way Double Door	4.000	Each	1622.64	6490.56	Rupees Six Thousand Four Hundred Ninety Paise FiftySix Only
112	Recessed sub main wiring alongwith earth wire with the following sizes of PVC insulated single core multistrand copper conductor ISI marked conforming to IS-694/1990 in 20mm dia non metallic heavy duty flexible conduit 1.6mm in surface / recessed PVC conduit as required (make of wire – Finolex / L & T / Anchor / Havells / V-Guard)					
	a. 2 x 6.0 sqmm. + 1 x 2.5 sq.mm.	100.000	Mtr.	189.13	18913.00	Rupees Eighteen Thousand Nine Hundred Thirteen Only
	b. 2 x 4 sqmm. + 1 x 1.5 sq.mm.	88.000	Mtr.	158.04	13907.52	Rupees Thirteen Thousand Nine Hundred Seven Paise
	c. 2 x 2.5 sqmm. + 1 x 1.5 sq.mm.	210.000	Mtr.	140.67	29540.70	Rupees TwentyNine Thousand Five Hundred Fourty Paise Seventy Only
	d. 2 x 1.5 sqmm. + 1 x 1.5 sq.mm.	90.000	Mtr.	126.07	11346.30	Rupees Eleven Thousand Three Hundred FourtySix Paise Thirty Only
	e. 1 x 1.5 sq.mm. (Inverter Wiring)	100.000	Mtr.	46.48	4648.00	Rupees Four Thousand Six Hundred FourtyEight Only
113	S/F of Bakelite angle holder / batten holder of ISI marked conforming to IS-1258/1987 in place of ceiling rose.	18.000	Each	16.00	288.00	Rupees Two Hundred EightyEight Only

SL NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
114	Supply and fixing earthing with G.I. earth pipe 3 mtr. long 40mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.					
	a. Standard earthing as per Govt. specification	1.000	Each	2359.00	2359.00	Rupees Two Thousand Three Hundred FiftyNine Only
115	Supply and fixing of 5 Amp. To 32A rating 240V "B" series MCB suitable for lighting and other loads of the following poles in the exiting MCB DB ISI marked complete with connections testing and commissioning etc. as required (Make – HPL / Havells / Legrand / L & T / C & S)					
	a. Single pole (SP)	24.000	Each	318.21	7637.04	Rupees Seven Thousand Six Hundred ThirtySeven Paise Four Only
	b. Double pole (DP)	4.000	Each	894.82	3579.28	Rupees Three Thousand Five Hundred SeventyNine Paise TwentyEight Only
	S/F of 63 Amp. Bus Bar	1.000	Each	6458.00	6458.00	Rupees Six Thousand Four Hundred FiftyEight Only
116	Supply and fixing of Modular fan regulator (Cona / Anchor / Usha / Bajaj)					
	a. Electronics step type Regulator (Modular type)	10.000	Each	291.00	2910.00	Rupees Two Thousand Nine Hundred Ten Only
117	Supply and fixing of 1200mm ceiling fan	4.000	Each	2378.87	9515.48	Rupees Nine Thousand Five Hundred Fifteen Paise FortyEight Only
118	S/F of 450mm exhaust fan	2.000	Each	2188.40	4376.80	Rupees Four Thousand Three Hundred SeventySix Paise Eighty Only
119	S/F of 60W LED Street Light	4.000	Each	7801.00	31204.00	Rupees ThirtyOne Thousand Two Hundred Four Only

Tumba

NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	ESTIMATED RATE	TOTAL AMOUNT WITH OUT TAX	TOTAL AMOUNT IN WORDS
120	S/F of 18W LED Tube Light	10.000	Each	678.18	6781.80	Rupees Six Thousand Seven Hundred EightyOne Paise Eighty Only
121	S/F of 9W LED Bulb	6.000	Each	169.65	1017.90	Rupees One Thousand Seventeen Paise Ninety Only

Total 4172036.00

I, Sri/smt \_\_\_\_\_ quote \_\_\_\_\_ % in ward \_\_\_\_\_ percent) excess over/less than/ equal to estimated rate, and my quoted amount is Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_ )

Signature of Contractor

No. of Over writing \_\_\_\_\_  
 No. of Correction \_\_\_\_\_  
 No. of Interpolation \_\_\_\_\_

Development Officer  
 Rayagada (Gajapati)

Assistant Engineer  
 NHM Gajapati

Tender schedule is Approved for Rs. 41,72,036.00 i.e.  
 Rupees Fortyone lakh Seventytwo thousand Thirty six ) only

21.9.2014  
 Addl. Executive Officer (Tech.)  
 Zilla Parishad, Gajapati