

OFFICE OF THE PANCHAYAT SAMITI, RAYAGADA

PO: RAYAGADA, PIN: 761213, DISTRICT: GAJAPATI, ODISHA


Identification No. - 1,2,3,4,5,6,7,8 & 9/ PS, Rayagada No. 80

Date:- 20.01.2021

The Block Development Officer, Rayagada on behalf of Governor of Odisha invites percentage rate bids in sealed cover for the construction of work detailed in the table from eligible Class of Contractors registered with the State Government and the Contractors of equivalent Grade / Class registered with the Central Government / MES / Railways for execution of Civil works. A bidder may submit the bid for one or more work out of the following works. The amount put to tender may be changed and confirmed at the time of sale of tender documents.

Sl. No.	Name of the Work and identification no.	Amount put to tender in rupees	EMD to deposit(1% of the tender amount)	Cost of tender documents including VAT @ 5% (non refundable)	Class of Contractor	Period of completion of the work
1	2	3	4	5	6	7
1	Construction of vented causeway on the road from Upper Landusahl to Titill of Laxmipur GP. Identification No. 1/2020-21 PS, Rayagada	12,05,649.00	12,057.00	Rs.6000/- + Rs. 300/-	D & C	Three months
2	Construction of vented cause way on the road from PWD road to Sandhigaon of Sanatundi GP . Identification No. 2/2020-21 PS, Rayagada	13,05,649.00	13,057.00	Rs.6000/- + Rs. 300/-	D & C	Three months
3	Const. of bridge on the from Hirapur to Rempi of Sanatundi GP . Identification No. 3/2020-21 PS, Rayagada	26,27,046.00	26,271.00	Rs.6000/- + Rs. 300/-	C & B	Six months
4	Const. of vented pipe causeway at Sankuda of Gangabada GP. Identification No. 4/2020-21 PS, Rayagada	17,47,220.00	17,473.00	Rs.6000/- + Rs. 300/-	D & C	Six months
5	Const. of box cell bridge connection between Akhada to Khambagaon of Gangabada GP. Identification No. 5/2020-21 PS, Rayagada	17,47,220.00	17,473.00	Rs.6000/- + Rs. 300/-	D & C	Six months
6	Const. of vented causeway on Oya-Elasara road near village Elasara of Kerandi GP. Identification No. 6/ 2020-21 PS, Rayagada	12,05,649.00	12,057.00	Rs.6000/- + Rs. 300/-	D & C	Three months
7	Const. of Check dam of field channel at Mahendranaya Nallo, Teraba of Koinpur GP . Identification No. 7/ 2020-21 PS, Rayagada	10,76,791.00	10,768.00	Rs.6000/- + Rs. 300/-	D & C	Three months
8	Renovation of Check dam across MT nalo near village Dungdung of Koinpur GP. Identification No. 8/ 2020-21 PS, Rayagada	15,76,476.00	15,765.00	Rs.6000/- + Rs. 300/-	D & C	Six months
9	Construction of bridge over Y.Engarsing Nalla at Y.Engarsing of Kerandi GP. Identification No. 9/ 2020-21 PS, Rayagada	19,93,827.00	19,939.00	Rs.6000/- + Rs. 300/-	D & C	Six months

The detail terms & conditions please visit our web site Gajapati.nic.in.


Block Development Officer,
Rayagada (Gajapati)

TERMS AND CONDITIONS.

1. The Tender paper containing specifications, the schedule of quantities and the set of Terms & Conditions of contract etc. will be available in the Websites <http://gajapati.nic.in> & <http://panchayat.gov.in/rayagadaip> from **25.01.2021 to 08.02.2021** and can be downloaded from the aforesaid Websites.
2. The Tenderer may download the tender paper from the website as specified and submit through Regd. Post / Speed post on or before **09.02.2021** the tender papers along with the required amount of tender cost of Rs.10,000/- (in case downloaded from website) in shape of Bank Draft / Bankers Cheque Issued in favour of the BDO, Rayagada payable at Rayagada. In this case the undersigned is not responsible for any addition, omission or deletion in the downloaded tender paper.
3. Bid document can be purchased from the Office of the undersigned on deposit of non-refundable fee in shape of BD/Banker's Cheque in favour BDO, Rayagada payable at Rayagada, Gajapati by **09.02.2021** or e-transferring (NEFT/RTGS) the amount to the Account No.80402200004465 of Syndicate Bank, Rayagada Branch in District Gajapati which stands in the name of the undersigned during office hours on all working days from **25.01.2021 to 08.02.2021**.
4. The EMD is to be deposited duly pledged in favour of BDO, Rayagada in shape of NSC/POTD/KVP along with the Tender paper, without EMD no tender paper will be entertained. Transfer or adjustment of EMD/differential/initial security deposit (ISD) will not be entertained.
5. Bank Draft/Banker's Cheque/NSC/POTD/KVP towards paper cost amount, EMD amount and differential amount should be submitted along with the Tender paper.
6. The tender paper have to be submitted in sealed cover (separately for each work) for the work indicating on the cover "TENDER PAPER FOR PANCHAYAT SAMITI, RAYAGADA" mentioning the name & ID number of the work on the top of the cover.
7. If the Tenderer quoted his rate more than 10% less of the scheduled amount, he should pledge the less amount i.e. difference between net quoted amount by the contractor and 90% of approved tender scheduled amount in favour of the B.D.O., Rayagada in shape of NSC/POTD/KVP etc. along with the tender paper.
8. The sealed tender paper must be accompanied with attested copies of valid and up to date GST for the year 2018-19, 2019-20 ITCC/PAN Card, valid contract license and EMD, No relationship Certificate, Bid security, Cost of documents (Non-refundable) as per column 5 above in separate envelop mentioning cost of tender papers and an affidavit about the authentication of documents produced without which the tenderer will be liable for rejection. The No-relation Certificate should be in the specific format as per OPWD F-2 clauses. Tenderers or their authorized representative should be present with their original documents for verification at the time of opening of tender.
9. The bids will be opened on **10.02.2021 at 11.00 am.** in the Office of the Panchayat Samiti, Rayagada located at Rayagada, Gajapati in presence of the Tender Committee & Bidders or their Authorized Agents who wish to attend. If the Office happens to be closed on the last date of the receipt of the bids as specified, the bids will be received and opened on the next working day at the same time and venue.
10. A Tenderer can submit only one tender paper for a particular work. Submission of more than one paper by the Tenderer for a particular tender or more than one work mentioning different percentage is liable for rejection of all such tender papers.
11. Non submission of any required documents and papers submitted without signature shall be liable for rejection.
12. The tender papers will be received by Registered Post / Speed Post only on or before **09.02.2021 by 05.00 PM.** No tender papers will be received by hand. The undersigned will not be responsible for any delay in postal services.

13. The defaulting / black-listed Contractor will not be allowed to participate in the above tender. An undertaking in this effect is mandatory.
14. No grace is allowed to SC & ST licensee unless claimed.
15. The Engineer contractors seeking exemption of EMD is to enclose an affidavit regarding the nos. of tenders they have participated with exemption of EMD during the current financial year 2019-20 & 2020-21.
16. The authority reserves the right to reject/cancel any or all tenders without assigning any reasons thereof at any point of time.

[Signature]
20.1.2021
Block Development Officer,
Rayagada.



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 1/2020-21 PS-Rayagada)

Name of the Work: : Constn. of verded Caseway on the road from U. Landwahi to Petali

Estimated Cost : Rs 15,00,000/-

Tender Value : Rs. 12,05,649/-

E.M.D : Rs. 12,057/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : D & C

Time of Completion : Three month

CONTRACTOR

Block Development Officer

Name of the work :- Const. of Vented Cause way on the road from Upper Landonaki to Titili of Lakshipur BP

Identification No:- 1/2020-21, PS - Rayagada

Name of the Bidder:-

1	Estimate Cost Put to Tender	Rs. 15,00,000/-
2	Amount put to Tender	Rs. 12,05,649/-
3	EMD required including VAT	Rs. 12,057/-
4	Time of completion	Rs. Three month.
5	Cost of Tender Paper including VAT	Rs. 6300/-
6	Class of contractor	D&C
7	Date of Sale & receipt of tender paper	25.01.21 to 08.02.2021 & 09.02.2021
8	Date of opening	10.02.2021

SCHEDULE OF WORKS

SI No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	128.86	Cum	292.89	Two hundred ninety two and eighty nine paise only	37742.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	18.79	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	18421.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering	151.86	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise	711417.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C	20.98	Qtl	7099.02	Seven thousand ninety nine and two paise only	148922.00
5	C C (1:2:4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	11.14	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	65328.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	13.10	Cum	1293.31	One thousand two hundred ninety three and thirty one paise only	16942.00
7	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling them after casting including cost of all materials complete.	424.70	Sqm	112.68	One hundred twelve and sixty eight paise only	47855.00
a	Foundation					
8	Supply and placing of NP4 1200 MM DIA hume pipe	37.50	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	200104.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost ,Conveyance royalty , Taxes of all material etc complete	1.60	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	10674.00

	cutting in disintegrated rock not required blasting to be removed by axes and crow bar and depositing material within 50 mtr Initial lead and 1.5 mtr Initial	30.00	Cum	449.62	Four hundred forty nine and sixty two paise only	13488.00
11	Collecting and stacking of moorum keeping in regular box heaps of 1.5mx1.5x.5m to be measured as 1.00 cum for premeasurement.	54.00	Cum	267.80	Two hundred sixty seven and eighty paise only	14461.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	54.00	Cum	375.83	Three hundred seventy five and eighty three paise only	20295.00
13	GST	12%				180000
	Total estimated cost in figure					Rs 1485649.00
	Total estimated cost in word	Fourteen lakh eighty five thousand six hundred forty nine only				

Total item only

I Sri/Smt..... S/O W/O.....
village..... Thana..... Post..... Quote..... % less
/ more/equal to estimated rate and my quoted value comes to Rs.....
Rupees(.....)only.

No. of correction
No. of over writings
No. of interpolations
Tender schedule is approved for Rs. 12,05,649/2 i.e. Rupees Twelve lakh five thousand six hundred forty nine only.



Signatur of the Contractor

Addl. Project Director, (Text) /
DRDA, Gajapati

K. Sankar
7-1-2014
Block Development Officer,
Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 2/2000-21 P.S. Rayagada)

Name of the Work: : Construction of rented Caserway on the road from PWD/panchto Sandya.

Estimated Cost : Rs 15,00,000/-

Tender Value : Rs. 13,05,649/-

E.M.D : Rs. 13,057/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : D&C

Time of Completion : Three month.

CONTRACTOR

Block Development Officer

Name of the work :-	Const. of Vented Cause way on the road from PUDD road to Sandhiguan of Kanatundi GP	
Identification No:-	2/2020-21, PS - Rayagada	
Name of the Bidder:-		
1	Estimate Cost Put to Tender	Rs. 15,00,000/-
2	Amount put to Tender	Rs. 13,05,649/-
3	EMD required including VAT	Rs. 1,20,571/-
4	Time of completion	Three month
5	Cost of Tender Paper including VAT	Rs. 6300/-
6	Class of contractor	D&C
7	Date of Sale & receipt of tender paper	25.01.2021 to 08.02.2021 & 09.02.2021
8	Date of opening	10.02.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	128.86	Cum	292.89	Two hundred ninety two and eighty nine paise only	37742.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	18.79	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	18421.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering and	151.86	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise	711417.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work	20.98	Qtl	7099.02	Seven thousand ninety nine and two paise only	148922.00
5	C C (1:2:4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	11.14	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	65328.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	13.10	Cum	1293.31	One thousand two hundred ninety three and thirty one paise only	16942.00
7	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling them after casting including cost of all materials complete.	424.70	Sqm	112.68	One hundred twelve and sixty eight paise only	47855.00
a	Foundation					
8	Supply and placing of NP4 1200 MM DIA hume pipe	37.50	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	200104.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost, Conveyance royalty, Taxes of all material etc complete	1.60	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	10674.00
10	Cutting in disintegrated rock not required blasting to be removed by access and crow bar and depositing material within 50 mtr initial lead and 1.5 mtr initial	30.00	Cum	449.62	Four hundred forty nine and sixty two paise only	13488.00

11	Collecting and stacking of moorum keeping in regular box heaps of 1.5m x 1.5m x 0.5m to be measured as 1.00 cum for premeasurement.	54.00	Cum	267.80	Two hundred sixty seven and eighty paise only	14481.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	54.00	Cum	375.83	Three hundred seventy five and eighty three paise only	20295.00
13	GST	12%				180000
Total estimated cost in figure						Rs 1485649.00
Total estimated cost in word						Fourteen lakh eighty five thousand six hundred forty nine only
Total Item only						

Sri/Smt..... S/O W/O.....
 Village..... Thana..... Post..... Quote..... % less
 more/equal to estimated rate and my quoted value comes to Rs.....
 rupees(.....)only.

o. of correction

o. of over writings

o. of interpolations.

Upward to

thousand

and

hundred

only

Tender Schedule is
 Rs. 13,05,649/- (ie. Rupees Thirteen Lakh five
 thousand six hundred forty nine) only

Signature of the Contractor

Addl. Project Director (Tech) x x |
 DRDA, Gajapati

Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 3/2020-21 P.S. Rayagada)

Name of the Work: : Construction of Bridge on the Road
from Herapura to Rempu (vertical
causeway)

Estimated Cost : Rs. 31,00,000/-

Tender Value : Rs. 26,27,046/-

E.M.D : Rs. 26,271/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : C & B

Time of Completion : Six Months.

CONTRACTOR

Block Development Officer

Name of the work :-	Const. of bridge on file from Henapur to Rempit	
Identification No.:-	3/2020-21	PS - Rayagada
Name of the Bidder:-		
1	Estimate Cost Put to Tender	Rs. 30,00,000/-
2	Amount put to Tender	Rs. 26,27,046/-
3	EMD required including VAT	Rs. 26,271/-
4	Time of completion	Six months
5	Cost of Tender Paper including VAT	Rs. 6300/-
6	Class of contractor	C & B
7	Date of Sale & receipt of tender paper	25.01.2021 to 08.02.2021 & 09.02.2021
8	Date of opening	10.02.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	233.16	Cum	292.89	Two hundred ninety two and eighty nine paise only	68290.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	35.54	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	34842.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering and	305.76	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise	1432329.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work	52.42	Qtl	7099.02	Seven thousand ninety nine and two paise only	372153.00
5	C C (1:2:4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	24.74	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	145083.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	15.31	Cum	1248.87	One thousand two hundred ninety three and thirty one paise only	19118.00
7	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling them after casting including cost of all materials complete.	606.94	Sqm	112.68	One hundred twelve and sixty eight paise only	68390
a	Foundation					
8	Supply and placing of NP4 1200 MM DIA hume pipe	67.50	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	360187.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost, Conveyance royalty, Taxes of all material etc complete	2.50	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	16678.00

10	Cutting in disintegrated rock not required blasting to be removed by access and crow bar and depositing material within 50 mtr initial lead and 1.5 mtr initial lift	90.00	Cum	449.82	Four hundred forty nine and sixty two paise only	40465.00
11	Collecting and stacking of moorum keeping in regular box heaps of 1.5mx1.5x.5m to be measured as 1.00 cum for premeasurement.	108.00	Cum	267.80	Two hundred sixty seven and eighty paise only	28922.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	108.00	Cum	375.83	Three hundred seventy five and eighty three paise only	40589.00
13	GST	12%				26,27,046
Total estimated cost in figure						360000
Total estimated cost in word						Rs 2987046.00
Total item only						Twenty Nine Lakh Eighty Seven Thousand Fourty six only

Sri/Smt..... S/O W/O.....
 Village..... Thana..... Post..... Quote..... % less
 more/equal to estimated rate and my quoted value comes to Rs.....
 rupees(.....)only.

No. of correction
 No. of over writings
 No. of interpolations
Tender schedule is approved for Rs. 26,27,046/- i.e. Rupees Twenty six lakh twenty seven thousand forty six only

[Signature]

Signatur of the Contractor

Addl. Project Director, (Tech.)
 DRDA, Gajapati

[Signature]
 7.11.2024

Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 4/2020-21 P.S Rayagada)

Name of the Work: : Construction of vented Pipe casing
at Samkudas

Estimated Cost : Rs 20,00000/-

Tender Value : Rs. 17,47,220/-

E.M.D : Rs. 17,473/-

Tender Paper Cost : Rs. 6200/-

Class of Contractor : D&C

Time of Completion : Six month.

CONTRACTOR

Block Development Officer

Name of the work :- **Constn of Vented pipe Causeway at Sankuda of Gangabada G.P**

Identification No:- **4/2020-21, PS - Rayagada**

Name of the Bidder:-

1	Estimate Cost Put to Tender	Rs. 20,00,000/-
2	Amount put to Tender	Rs. 17,47,220/-
3	EMD required including VAT	Rs. 17,47,220/-
4	Time of completion	Six month
5	Cost of Tender Paper including VAT	Rs. 6300/-
6	Class of contractor	D & C
7	Date of Sale & receipt of tender paper	25.01.2021 to 08.02.2021 & 09.02.2021
8	Date of opening	10.02.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	162.54	Cum	292.89	Two hundred ninety two and eighty nine paise only	47608.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	24.21	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	23734.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering and laying the concrete to the required level including vibrating for compaction and curing etc complete as per direction of the Engr-in-charge.	205.49	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise only	962616.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work including all taxes, cost, conveyance and all other charges etc. Including cost of binding wire of 18 gauge and labour charges requirs for the work in all floors as per direction of the Engr- in-charge.	34.57	Qty	7099.02	Seven thousand ninety nine and two paise only	245402.00
5	C C (1;2;4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	13.83	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	81103.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	13.75	Cum	1293.31	One thousand two hundred ninty three and thirty one paise only	17783.00
7	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling them after casting including cost of all materials complete.	478.30	Sqm	112.68	One hundred twelve and sixty eight paise only	53895.00
a	Foundation					

8	Supply and placing of NP4 1200 MM DIA hume pipe	45.00	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	240125.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost ,Conveyance royalty ,Taxes of all material etc complete	1.92	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	12809.00
10	Cutting in disintegrated rock not required blasting to be removed by access and crow bar and depositing material within 50 mtr initial lead and 1.5 mtr initial	30.00	Cum	449.62	Four hundred forty nine and sixty two paise only	13488.00
11	Collecting and stacking of moorum keeping in regular box heaps of 1.5mx1.5x.5m to be measured as 1.00 cum for premeasurement.	75.60	Cum	267.80	Two hundred sixty seven and eighty paise only	20246.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	75.60	Cum	375.83	Three hundred seventy five and eighty three paise only	28413.00
13	GST 12%					240000
Total estimated cost in figure						Rs 1987220.00
Total estimated cost in word						Nineteen Lakh Eighty Seven Thousand Two hundred Twenty only
Total item only						

Sri/Smt..... S/O M/O.....
 Village..... Thana..... Post..... Quote..... % less
 more/equal to estimated rate and my quoted value comes to Rs.....
 rupees(.....)only.

No. of correction
 No. of over writings
 No. of interpolations
 approved for Rs 17,47,220/- (Rupees Seventeen Lakh forty seven thousand two hundred twenty only).

Signature of the Contractor

Addl. Project Director, (Tech)
 DRDA, Gajapati

Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 5/2000-21 PS Rayagada)

Name of the Work: : Construction of Boxcell Bridge

Estimated Cost

: Connection between Akhela to
Khambagar created Pipe Caweway
Rs 20,00000/-

Tender Value

: Rs. 17,47,920/-

E.M.D

: Rs. 17,473/-

Tender Paper Cost

: Rs. 6300/-

Class of Contractor

: D&E

Time of Completion

: Six months

r
CONTRACTOR

Block Development Officer

Name of the work - Construction of box cell bridge construction between Akhoda to Khambragam	
Identification No. 5/2020-9.1- PS - Rayagada	
Name of the Bidder -	
1	Estimate Cost Put to Tender Rs 90 00 000/-
2	Amount put to Tender Rs 17 47 220/-
3	EMD required including VAT Rs 17 47 220/-
4	Time of completion Six months
5	Cost of Tender Paper including VAT Rs 6300/-
6	Class of contractor D&C
7	Date of Sale & receipt of tender paper
8	Date of opening

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	162.54	Cum	292.89	Two hundred ninety two and eighty nine paise only	47606.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	24.21	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	23734.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering and laying the concrete to the required level including vibrating for compaction and curing etc complete as per direction of the Engr-in-charge.	205.49	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise only	962616.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work including all taxes, cost, conveyance and all other charges etc. Including cost of binding wire of 18 gauge and labour charges requires for the work in all floors as per direction of the Engr- in-charge.	34.57	Qtl	7099.02	Seven thousand ninety nine and two paise only	245402.00
5	C C (1:2:4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	13.83	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	81103.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	13.75	Cum	1293.31	One thousand two hundred ninty three and thirty one paise only	17783.00
7	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling them after casting including cost of all materials complete.	478.30	Sqm	112.68	One hundred twelve and sixty eight paise only	53895.00
a	Foundation					

8	Supply and placing of NP4 1200 MM DIA hume pipe	45.00	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	240125.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost, Conveyance royalty, Taxes of all material etc complete	1.92	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	12809.00
10	Cutting in disintegrated rock not required blasting to be removed by access and crow bar and depositing material within 50 mtr initial lead and 1.5 mtr initial	30.00	Cum	449.62	Four hundred forty nine and sixty two paise only	13488.00
11	Collecting and stacking of moorum keeping in regular box heaps of 1.5mx1.5x.5m to be measured as 1.00 cum for premeasurement.	75.60	Cum	267.80	Two hundred sixty seven and eighty paise only	20246.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	75.60	Cum	375.83	Three hundred seventy five and eighty three paise only	28413.00
13	GST	12%				Rs 17,47,220
Total estimated cost in figure						240000
Total estimated cost in word						Rs 1987220.00
Total item only						Nineteen Lakh Eighty Seven Thousand Two hundred Twenty only

Sri/Smt..... S/O W/O.....
village..... Thana..... Post..... Quote..... % less
more/equal to estimated rate and my quoted value comes to Rs.....
Rupees(.....)only.

No. of correction

No. of over writings *Tender schedule is*

No. of interpolations
approved for Rs. 17,47,220/- i.e. Rupees Seventeen lakh forty seven thousand two hundred twenty only

[Signature]

Signatur of the Contractor

Addl. Project Director (Tech) No 1
DRDA, Gajapati

[Signature]
7.10.2018
Block Development Officer,
Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 6/2000-21 PS Rayagada)

Name of the Work: : Construction of verted Caweway
on oya Ellasara Road near
village Ellasara.

Estimated Cost : Rs 15,00000/-

Tender Value : Rs. 12,05,649/-

E.M.D : Rs. ~~12,05,649/-~~ 12,057/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : D&C

Time of Completion : Three months.

CONTRACTOR

Block Development Officer

Name of the work :- Const. of Vented Gussaway on Dya-Ebana road near village
Lasana of Khandi GP

Identification No:- 6/2020-21, PS - Rayagada

Name of the Bidder:-

1	Estimate Cost Put to Tender	Rs. 15,00,000/-
2	Amount put to Tender	Rs. 12,05,649/-
3	EMD required including VAT	Rs. 12,057/-
4	Time of completion	Three months.
5	Cost of Tender Paper including VAT	Rs. 6,900/-
6	Class of contractor	D & C
7	Date of Sale & receipt of tender paper	25.01.2021 to 08.02.2021 & 09.02.2021
8	Date of opening	10.02.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	128.86	Cum	292.89	Two hundred ninty two and eighty nine paise only	37742.00
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	18.79	Cum	980.35	Nine Hundred eighty and Thirty five Paise only	18421.00
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering	151.86	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise	711417.00
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C	20.98	Qtl	7099.02	Seven thousand ninty nine and two paise only	148922.00
5	C C (1:2:4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	11.14	Cum	5864.30	Five thousand eight hundred sixty four and thirty paise	65328.00
6	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	13.10	Cum	1293.31	One thousand two hundred ninty three and thirty one paise only	16942.00
7	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling them after casting including cost of all materials complete.	424.70	Sqm	112.68	One hundred twelve and sixty eight paise only	47855.00
a	Foundation					
8	Supply and placing of NP4 1200 MM DIA hume pipe	37.50	Rmtr	5336.10	Five thousand three hundred thirty six and ten paise only	200104.00
9	RCC(1:1.5:3) with 12 mm size H.G Chips including cost, Conveyance royalty, Taxes of all material etc complete	1.60	Cum	6671.16	Six thousand six hundred seventy one and sixteen paise only	10674.00

10	Cutting in disintegrated rock not required blasting to be removed by axes and crow bar and depositing material within 50 mtr initial lead and 1.5 mtr initial	30.00	Cum	449.62	Four hundred forty nine and sixty two paise only	13488.00
11	Collecting and stacking of moorum keeping in regular box heaps of 1.5mx1.5x.5m to be measured as 1.00 cum for premeasurement.	54.00	Cum	267.80	Two hundred sixty seven and eighty paise only	14461.00
12	Conveying from stacks and spreading of moorum on road surface and consolidation	54.00	Cum	375.83	Three hundred seventy five and eighty three paise only	20295.00
13	GST	12%				180000
Total estimated cost in figure						Rs 1485649.00
Total estimated cost in word						Fourteen lakh eighty five thousand six hundred forty nine only
Total item only						


Sri/Smt..... S/O N/O.....
 Village..... Thana..... Post..... Quote..... % less
 more/equal to estimated rate and my quoted value comes to Rs.....
 rupees(.....)only.

a. of correction
 b. of over writings
 c. of interpolations.
 Tender schedule is approved for Rs. 12,05,649/- i.e. Rupees Twelve Lakh five thousand six hundred forty nine only.



Signatur of the Contractor

Addl. Project Director (Tech.)
 DRDA, Gajapati



Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. ... 7/2020-21 P.S. Rayagada)

Name of the Work: : Construction of check dam & field
channel at Mahendrapur Panchayat, Rayagada.

Estimated Cost : Rs. 2,00,000/-

Tender Value : Rs. 10,76,791/-

E.M.D : Rs. 10,768/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : D&R

Time of Completion : Three months

CONTRACTOR

Block Development Officer

Name of the work :- Construction of Check Dam & Field Channel at Mahendratannya Nalo, Teraba of Kowpur GP	
Identification No:-	F/2020-21 PS - Rayagada
Name of the Bidder:-	
1	Estimate Cost 12. 12.00.000/-
2	Amount put to Tender 16. 10.76.791/-
3	EMD required including VAT 10,768/-
4	Time of completion Three months
5	Cost of Tender Paper including VAT 14.6300/-
6	Class of contractor D&P
7	Date of Sale & receipt of tender paper 25.01.2021 to 08.02.2021 & 09.02.2021
8	Date of opening 10.09.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work excavation in foundation in stony soil in foundation and plinth including rough dressing and levelling the bed and depositing the excavated earth away from the work site with all leads and lifts including cost of all labour and T&P required for the work and etc. complete in all respect and as per the direction by the Engineer-in-charge.	118.80	cum	292.89	Two hundred ninety two and eighty nine paise only	34795.00
2	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc.complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge	71.25	cum	5023.14	Five Thousand Twenty Three and Fourteen Paise oly	357898.00
3	RCC work of m 20 grade with 20 mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying	82.24	cum	5500.29	Five thousand five hundred and twenty nine paise only	452322.00
4	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling them after casting including cost of all materials complete.	213.00	Sqm	112.68	One hundred twelve and sixty eight paise only	24001.00
5	Supplying of HYSD steel for R C C work including cost of MS bar with cutting,bending,binding and tying and placing in position as required for R C C work including all taxes,cost,conveyance and all other charges etc. Including cost of binding wire of 18 gauge and labour charges requirs for the work in all floors as per direction of the Engr- in-charge.	19.58	Qntl	7099.02	Seven thousand ninety nine and two paise only	138963.00
6	20mm th grading plaster in C.M (1:4) over roof slab including all cost, conveyance, royalty, taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge.	189.00	Sqm	213.09	Two hundred thirteen and nine paise only	40274.00
7	C C (1;2;4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes,cost,conveyance and royalty etc as per direction of the Engr-in-charge.	4.50	cum	6341.89	Six thousand three hundred forty one and eighty nine paise only	28538.00
GST @12						120000.00
Total estimated cost in figure						1196791.00
Total estimated cost in word						Eleven Lakh ninety six thousand seven hundred ninety one only

Total item only

I Sri/Smt..... S/O /W/O.....
 village.....Thana.....Post.....Quote.....% less
 / more/equal to estimated rate and my quoted value comes to Rs.....
 Rupees(.....)only.

No. of correction
 No. of over writings
 No. of interpolations
 Tender schedule is approved for Rs 10,76,791/- Coe. Papers Ten lakh seventy six thousand seven hundred ninety one only.

Signature of the Contractor

Addl. Project Director (Tech.)
 DRDA, Gajapati

Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 8/2020-21, P.S. Rayagada's)

Name of the Work: : Renovation of Checkdam across
MT Nala near village Durgam

Estimated Cost : Rs. 18,00,000/-

Tender Value : Rs. 15,76,476/-

E.M.D : Rs. 15,76,476/-

Tender Paper Cost : Rs. 6300/-

Class of Contractor : D & C

Time of Completion : Six months.

CONTRACTOR

Block Development Officer

Name of the work :- Renovation of Check Dam across Mahendra Tanaya Nalo near Village Dungdung	
Identification No:- 87920-2/PS Rayagada	
Name of the Bidder:-	
1	Estimate Cost (Rs. 18,00,000/-)
2	Amount put to Tender (Rs. 15,76,476/-)
3	EMD required including VAT (Rs. 1,57,657/-)
4	Time of completion Six month
5	Cost of Tender Paper including VAT (Rs. 6300/-)
6	Class of contractor B & C
7	Date of Sale & receipt of tender paper 25.01.2021 to 08.09.2021 & 09.09.2021
8	Date of opening 10.09.2021

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount Rs P
				Figure	Words	
1	Earth work excavation in foundation in stony soil in foundation and plinth including rough dressing and levelling the bed and depositing the excavated earth away from the work site with all leads and lifts including cost of all labour and T&P required for the work and etc. complete in all respect and as per the direction by the Engineer-in-charge.	145.80	cum	292.89	Two hundred ninety two and eighty nine paise only	42703.00
2	Cement Concrete of proportion(1:3:6) in foundation and plinth using 4cm size clean hard black granite metal of approved quality from approved quarry including hoisting, lowering and laying in layers not exceeding 15cm thick to the required level, ramming watering and curing etc. complete including cost, conveyance, royalty taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge	124.40	cum	5023.14	Five Thousand Twenty Three and Fourteen Paise oly	624878.00
3	RCC work of m 20 grade with 20 mm and down grade black hard granite (Crusher broken) stone chips including hoisting and laying	103.04	cum	5500.29	Five thousand five hundred and twenty nine paise only	566728.00
4	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling them after casting including cost of all materials complete.	422.40	Sqm	112.68	One hundred twelve and sixty eight paise only	47596.00
5	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work including all taxes, cost, conveyance and all other charges etc. Including cost of binding wire of 18 gauge and labour charges requirs for the work in all floors as per direction of the Engr-in-charge.	28.57	Qntl	7099.02	Seven thousand ninety nine and two paise only	202791.00
6	20mm th grading plaster in C.M (1:4) over roof slab including all cost, conveyance, royalty, taxes of all the materials required for the work with all labour, T&P etc. complete in all respect as per specification and direction of the Engineer-in-charge.	270.00	Sqm	213.09	Two hundred thirteen and nine paise only	57534.00
7	C C (1;2;4) using 12mm HGCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	5.40	cum	6341.89	Six thousand three hundred forty one and eighty nine paise only	34246.00
	GST @12					210000.00
	Total estimated cost in figure					1786476.00
	Total estimated cost in word					Seveteen Lakh eighty six thousand four hundred seventy six only

Total item only

I Sri/Smt..... S/O/W/O.....
 village.....Thana.....Post.....Quote.....% less
 / more/equal to estimated rate and my quoted value comes to Rs.....
 Rupees(.....)only.

No. of correction
 No. of over writings
 No. of interpolations
 Rs. 15,76,476/- i.e. Rupees fifteen lakh seventy six thousand four hundred seventy six only

Signature of the Contractor

Add. Project Director, (Tech.)
 DRDA, Gajapati

Block Development Officer,
 Rayagada



GOVERNMENT OF ODISHA

PANCHAYATI RAJ DEPARTMENT

PANCHAYAT SAMITI, RAYAGADA

DETAILED TENDER CALL NOTICE
WITH SECHDULE OF QUANTITIES

(.....)

(Identification No. 9/200021 P. Rayagada)

Name of the Work: Construction of Bridge over
Y. Engarsing Nalla at Y. Engarsing

Estimated Cost : Rs 22,80,000/-

Tender Value : Rs. 19,93,827=00

E.M.D : Rs. 19,939=00

Tender Paper Cost : Rs. 6000=00 + VAT Rs. 300=00

Class of Contractor : D&C

Time of Completion : Six month

CONTRACTOR

Block Development Officer

Name of the work :-	Constructing bridge over Yengoneeri nalla at Yengoneeri		
Identification No:-	9/2020-21	PS - Rayagada	
Name of the Bidder:-			
1	Estimate Cost Put to Tender	₹ 22,80,000/-	
2	Amount put to Tender	₹ 19,92,829/-	
3	EMD required including VAT	₹ 6,800/- 19,92,829/-	
4	Time of completion	Six month	
5	Cost of Tender Paper including VAT	₹ 6,300/-	
6	Class of contractor	D&C	
7	Date of Sale & receipt of tender paper	25.01.2021 to 17.02.2021 & 09.02.2021	
8	Date of opening	10.02.2021	

SCHEDULE OF WORKS

Sl No.	Description of works	No. or Quantity	Unit	Estimate rate		Amount	
				Figure	Words	Rs	P
1	Earth work in excavation of foundation and plinth in stoney Earth or gravelly soil within initial lead and lift and dressing the bed and side as per depth provided in design and disposal the excavated material away from the site including dewatering and clean the site as necessary etc complete and as per direction of the Engr-in-charge.	235.93	Cum	292.89	Two hundred ninety two and eighty nine paise only	69101.00	
2	Supplying and filling in F & P using filling sand duly watering and ramming including all cost, conveyance and royalty etc complete as per direction of the Engr-in-charge.	9.69	Cum	980.35	Nine Hundred eighty and Thirty Paise only	9500.00	
3	Cement concrete of proportion (1:3:6) using 40mm size of CBHG stone metal for foundation and plinth from approved quarry including hoisting, lowering and laying the concrete to the required level including vibrating for compaction and curing etc complete as per direction of the Engr-in-charge.	14.10	Cum	4684.54	Four thousand six hundred eighty four and fifty four paise only	66052.00	
4	Supplying of HYSD steel for R C C work including cost of MS bar with cutting, bending, binding and tying and placing in position as required for R C C work including all taxes, cost, conveyance and all other charges etc. Including cost of binding wire of 18 gauge and labour charges requires for the work in all floors as per direction of the Engr- in-charge.	44.65	Qtl	7099.02	Seven thousand ninety nine and two paise only	316948.00	
5	RCC work of M25 grade with 20 mm and down grade black hard granite (Crusher Brocken) stone chips including hosting and laying	201.14	Cum	6099.22	Six thousand ninety nine and twenty two paise pny	1226797.00	
6	RCC (1:1.5:3) Using 12 mm Size Chips hard black granite chips of approved quality from approved Quarry including hoisting ,Lowering and laying Concrete with necessary slope and smoothness to receive tar felting or terracing watering and curing for four weeks centring shuttering and finishing the exposed surface and ceiling smooth surfce including cost, conveyance, royalty taxes etc. complete	20.51	Cum	10692.42	Ten thousand Six hundred ninety two and forty two paise only	219302.00	

7	C C (1;2;4) using 12mm HQCB stone chips from approved quarry to proper slope including curing and watering with all taxes, cost, conveyance and royalty etc as per direction of the Engr-in-charge.	3.65	Sqm	5864.30	Five thousand eight hundred sixty four and thirty paise only	21405
8	RR Stone Packing with 30 cm size HG Stone boulder including cost Conveyance Royalty taxes of all materials required for the work with all labour T&P etc. Complete in all respect as per specification and direction of the Engineer-In Charge	24.00	Rmtir	1283.31	One thousand two hundred ninety three and thirty one paise only	31039.00
9	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling them after casting including cost of all materials complete.	298.92	Cum	112.68	One hundred twelve and sixty eight paise only	33683.00
	a) Foundation					19,93,827
13	GST	12%				273600
	Total estimated cost in figure					Rs 2267427.00
	Total estimated cost in word	put in tender			Twenty-two lakh sixty seven thousand four hundred twenty seven only	Nineteen lakh ninety three thousand eight hundred twenty seven only

Total item only

Eight hundred twenty seven only

Sri/Smt..... S/O /W/O.....
 village..... Thana..... Post..... Quote..... % less
 / more/equal to estimated rate and my quoted value comes to Rs.....
 Rupees(.....)only.

No. of correction

No. of over writings

No. of Interpolations.

Tender schedule approved for 2.19,93,827/-
 i.e. Rupees nineteen lakh ninety three thousand eight hundred twenty seven only

Addl. Project Director (Tech.)
 DRDA, Gajapati 16.01.2011

Block Development Officer,
 Rayagada