



**ODISHA PVTG EMPOWERMENT & LIVELIHOODS IMPROVEMENT
PROGRAMME LSDA, SERANGO: GAJAPATI**



No:- 76 /2019 /OPELIP LSDA , Dt. - 12-02-2019

TENDER CALL NOTICE - 02/18-19

The Special Officer, L.S.D.A., Serango invites percentage rate sealed Tenders in Prescribed format for following work to be eventually drawn up in the P.W.D. F2 Forms in conformity with the detailed Tender Call Notice from the eligible Govt. Registered Contractors of P.W.D./ N.H./ Railway contractor/ Water Resources / P.H.D. /R.D. Department, Govt. of Orissa/C.P.W.D belonging to the class as noted in respect of following work.

| Sl. No | Name of the Work | Amount put to tender (A) | Class of Contractor | Cost of Tender Paper (A) | EMD @ 1 % (A) | Time of Completion |
|--------|---|--------------------------|---------------------|--------------------------|---------------|-------------------------|
| 1 | Construction of work shed for producer Group in LSDA, Serango under OPELIP 2018-19. | ₹.24,55,135/- | 'C' & 'B' | ₹. 6000/- | ₹.24,600/- | 6 (Six calendar months) |


| | | |
|-------------------------------|---|---|
| Date of sale of Tender papers | : | From 15.02.2019 to 25.02.2019 (From 10.00A.M. to 5.00 P.M. on Working days only at Office of LSDA, Serango) |
| Date of receipt of tender * | : | From 15.02.2019 to 26.02.2019 (From 10.00A.M. to 5.00 P.M. on Working days only at Office of LSDA, Serango) |
| Mode of Receipt of tender | : | By Regd. Post with AD / Speed Post / By hand (In person Drop Box) ONLY, On working days only. No other mode will be accepted. |
| Date of opening of tender ** | : | On 27.02.2019 at 11.00 A.M. in Office chamber of PA, ITDA, Paralakhemundi. |

EMD required against the work should be enclosed along with the tender duly pledged in favour of Special Officer, LSDA, Serango in shape of NSC/KVP/Time Deposit of any Nationalized bank / Pass Book of Post office / deposit receipt of schedule bank etc. The cost of Tender Paper for each work as noted above should be deposited along with application by Bank Draft drawn in favour of Special Officer, LSDA, Serango (not refundable) payable at SBI, Serango. The photo copy of valid contract License, GST clearance certificate, PAN card & labour license duly self attested are to be furnished along with the tender. The Tenderers are required to furnish an affidavit about the Authenticity of Tender documents along with the Tender paper. The tenders without the above documents and E.M.D. will be rejected. The Authority will not be responsible for any Postal delay for receipt of the Tender papers in this office. The Tenders will be opened on the date notified above in presence of tenderers or their authorized agents. The Tenderers are to submit the original license to the tender committee at the time of tender opening for scrutiny. The authority reserves the right to reject any or all tenders without assigning any reason thereof. The decision of the Tender Committee shall be final and binding. The successful tenderers are required to execute an Agreement in F-2 format and submit the work programme on receipt of the work order. The tenderers are

required to produce all records / documents in original, the photocopy of which has been attached to the Tender paper.

Condition-1: The Engineering contractors seeking exemption of EMD have to produce their original license at the time of opening of tender for entering of EMD exemption since they can be awarded maximum in three works in a financial year with such exemption.


Condition-2: As per amendment to para 3.5.5 (V) of note:2 of OPWD code volume-I by modification. Official memorandum No.5288, dated 04.05.2016 of works Department- Additional performance security shall be deposited by the successful bidder when the bid amount is unbalanced that is less than the estimated cost put to tender, in such an event, the successful bidder who have quoted less bid price/rate then the estimated cost put to tender, shall have to furnish the exact amount of difference cost i.e estimated cost put to tender (-) the quote, as Addl. Performance Security in shape of Post office, Bank Account (NSC/POTD account/KVP/Deposit receipt of schedule Bank) duly pledged in favour of Special Officer, LSDA, Serango within 07 (seven) days from the date of intimation about success of the tender.


Special Officer,
LSDA, Serango

Memo No.- 77

Dt.- 12-02-2019

Copy submitted to the Commissioner-cum-Secretary to Government, ST & SC Development Department, Odisha, Bhubaneswar for favour of kind information.


Special Officer,
LSDA, Serango

Memo No.- 78

Dt.- 12-02-2019


Copy submitted to the Director (ST)-cum-Additional Secretary to Govt., ST & SC Development Department, Odisha, Bhubaneswar for favour of kind information.


Special Officer,
LSDA, Serango

Memo No.- 79

Dt.- 12-02-2019


Copy submitted to the Director (SC)-cum-Special Secretary to Govt., ST & SC Development Department, Odisha, Bhubaneswar for favour of kind information.


Special Officer,
LSDA, Serango

Memo No.- 80

Dt.- 12-02-2019


Copy submitted to the Programme Director, OPELIP, Bhubaneswar for kind information.


Special Officer,
LSDA, Serango

Memo No- 81 /

Copy submitted to the Collector, Gajapati for favour of kind information.


Dt.- 12-02-2019


Special Officer,
LSDA, Serango

Dt.- 12-02-2019

Memo No- 82 /


Copy submitted to the Project Administrator for favour of kind information.


Special Officer,
LSDA, Serango

Dt.- 12-02-2019

Memo No.- 83

Copy to the Executive Engineer DRDA, Gajapati Paralakhemundi for information and necessary action. He is requested to attend the Tender Committee meeting at the office chamber of PA, ITDA, Paralakhemundi on 27.02.2019 at 11.00 A.M.



Special Officer,
LSDA, Serango

Dt.- 12-02-2019

Memo No- 84 /

Copy submitted to the Sub Collector, Paralakhemundi / Special Officer, SDA, Chandragiri / Executive Engineer, M.I. Division, Gajapati/Executive Engineer, R & B Division, Gajapati/Executive Engineer, RWS & S Division, Gajapati / Executive Engineer, Rural Works Division, Paralakhemundi /All Block Development Officers of Gajapati District/All Tahasildars of Gajapati District /All Local Offices with a request to cause publication of the Notice in their Office Notice Board for information and wide circulation.


Copy to Office Notice Board of this office for information all concerned for wide publication.


Special Officer,
LSDA, Serango

Dt.- 12-02-2019


Memo No- 85 /

Copy forwarded to the DIO, NIC, Paralakhemundi for information and necessary action. He is requested to upload the tender in the website for wide publication.


Special Officer,
LSDA, Serango

Memo No- 86 /

Copy to the Asst-Executive Engineer, ITDA, Paralakhemundi / Junior Engineer & Accountant of LSDA, Serango for information and necessary action. The Asst-Executive Engineer, ITDA, Paralakhemundi is requested to attend the Tender Committee meeting at the office chamber of P.A, ITDA, on 27.02.2019 at 11.00 A.M.


Special Officer,
LSDA, Serango

Dt.- 12-02-2019



Lanjia Soura Development Agency, Serango, Gumma Block, Gajapati.

INVITATION of Sealed Tender

Sealed Tender is invited in the prescribed format for construction of Work Shed for Producer Group in the office Premises of LSDA, Serango. Eventually drawn up in the PWD F2 forms in conformity with the detailed tender call Notice No-2 Of 2018-2019 of LSDA Serango from the interested Govt. Regd. contractors of PWD, PH, water resources PHD/RD department of Govt of Odisha and CPWD and railway contractors. The interested contractors may visit the website of : -www.gajapati.nic.in & <http://www.opelip.org> for details.

1. Name of the Work: **Construction of Work Shed for Producer Group at LSDA, Serango, Gumma Block, Gajapati Dist.**
2. Construction of Work Shed Cost : **Rs 30,00,000/-**
3. Class of Contractor: **'C' Class / 'B' Class**
4. Period of Completion: **06 calendar months.**
5. Sale of tender Papers from **15/2/2019 to 25/02/2019** time **11.00 A.M to 4.00 P.M** on all working Days.
6. Last date and Time to receive the Tender : **Date: 26 .02.2019 at 5 PM**
7. Name and Address of officer inviting Tender: **Special officer, LSDA, Serango, Gumma Block, Gajapati. Tenders are strictly instructed to submit their Tender through one medium i.e hard copy by registered post / Speed post only. Sealed bid must be delivered on or before 26.02.2019 by 5.PM at office of the Lanjia Soura Development Agency , Serango-761207, Serango, Gumma Block, Gajapati District- Odisha.**

The Special Officer reserves the right to accept or reject any or all tender without assigning any reason thereof.

By order of Collector Gajapati cum Chairman LSDA, OPELIP, Serango

Sd/-

Date: 14 .02.2019

Place: Serango

Special Officer

LSDA-Serango

TENDER SCHEDULE

NAME OF THE WORK:- CONSTRUCTION OF WORKSHED FOR PRODUCER GROUP INSIDE THE PREMISES OF OFFICE OF LSDA SERANGO UNDER GUMMA BLOCK

| SL. NO. | ITEMS | QUANTITY | UNIT | RATE | Amount |
|---------|---|-------------|---------|----------|--------|
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Earth work in excavation of foundation trenches & Columns in all kinds of soil within all lead and lifts including dressing the sides, shoring (if necessary), bailing out water and leveling the bed and depositing the excavated materials away from the work site including all costs of labour, sundries, tools & plants required for the work etc. complete as per direction of Engineer-in-Charge. | 122.74 Cum. | 1 Cum. | 181.53 | 22281 |
| 2 | Filling in foundation and Plinth with sand well watered and rammed & dressed & level to proper gradient including all cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer in Charge. | 121.09 Cum. | 1 Cum. | 639.13 | 77392 |
| 3 | Cement concrete (1:3:6) with 4cm size size hand broken hard granite metals of approved quality including mixing with concrete mixture, lowering & laying in layers not exceeding 300 mm. in depth, ramming compacting to proper thickness, watering, curing for required period including all cost, conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge. | 64.13 Cum. | 1 Cum. | 4156.13 | 266533 |
| 4 | Rainforced cement concret M-20 grade using 20mm and down graded size crusher broken hard granite chips of approved quality including mixing with concrete mixture. including hoisting and laying in position & compacting with vibrator to proper design section including all the cost, conveyance, royalty & taxes of all materials, labour, rigid smooth centering, shuttering and dismantling the same after 28 days of casting, watering, curing etc. complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | | | | |
| i) | Column Base and Footing | 26.69 Cum. | 1 Cum. | 5023.65 | 134081 |
| ii) | Plinth Band | 18.42 Cum. | 1 Cum. | 5274.55 | 97157 |
| iii) | Column and Beam | 13.95 Cum. | 1 Cum. | 11623.84 | 162153 |
| iv) | Lintel | 1.29 Cum. | 1 Cum. | 8468.90 | 10925 |
| v) | Roof Slabs | 8.99 Cum. | 1 Cum. | 8952.29 | 80481 |
| vi) | Chajjas | 4.50 Sqm. | 1 Sqm. | 753.28 | 3390 |
| 5 | Supplying HYSD/Tor steel reinforcement from SAIL, VIZAG STEEL OR TATA STEEL brand of required diameter of approved quality including Labour charges for cutting, bending, binding and tying the grills and placing in position including cost, conveyance & taxes of reinforcements conforming to ISI standard and binding wire 18 to 20 gauge and as per drawing, design etc. complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | 73.84 Qtls. | 1 Qtls. | 6338.99 | 468071 |
| 6 | 9" thick Flyah Bricks in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 kg/cm ² immersing the bricks in water not less than six hours before use in masonry including watering and curing for required period with all cost conveyance, royalty, taxes of all materials etc. complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | 39.92 Cum. | 1 Cum. | 4301.29 | 171707 |
| 7 | 16 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | 173.76 Sqm. | 1 Sqm. | 184.12 | 31993 |

| Sl. NO. | ITEMS | QUANTITY | UNIT | RATE | Amount |
|---------|--|----------|------|--------|-----------|
| 1 | 2 | 3 | 4 | 5 | 6 |
| 8 | 12 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, labour, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | | | | |
| 9 | Fixing Vitrified tiles in floors trades or steps and landing on 25mm thick bed of C.M (1:1) jointed with neat cement slurry mixed with pigment to match shed of the tiles including rubbing and polishing etc complete. | 210.72 | Sqm | 155.47 | 32761 |
| a) | Ground Floor | | | | |
| b) | 2.5cm thick A.S.Flooring in c.c. (1:2:4) using 12mm size c.b. h.g. chips. | 68.75 | Sqm. | 949.39 | 65271 |
| | Ground Floor | | | | |
| 10 | Providing, fitting and fixing of M.S panelled doors Windows double leaved shutters with M.S frames made out up the following materials conforming to relevant ISS, ISI frames:- 35 x 35 x 6mm M.S. Angles, shutter style:- Top & Bottom rill 25 x 25 x 3mm M.S Angle, door panel:- 1mm CR Sheet. Panel stiffener covering width of each leaf:- 19.50mm, M.S.Flat 3 Nos. on each leaf. Hinges size:- 100mm 6 Nos.(3Nos of each side) but out as per ISS. Hold fast:- 35 x 35 x 6mm M.S Angle 175mm length bifurcated at the tip 3 nos of each side: Handle:19mm M.S Flat 4 nos. fabricated. Aldrop:- 2 nos. bought out as per ISS etc. complete as per the direction of Engineer-in-Charge.(EPM rate) | 202.56 | Sqm. | 287.89 | 58315 |
| a) | Ground Floor | 617.40 | Kg | 76.26 | 47082.92 |
| 11 | 2.5cm thick grading concrete in C.C. (1:2:2) using 10mm & down graded crusher broken hard granite chips for roof making proper slope as per requirement on roof including the cost of all labour materials, leak proofing chemicals sico or equivalent as per ISI Code etc. complete as per the direction of Engineer-in-Charge. | | | | |
| b) | First Floor | 71.92 | Sqm. | 276.51 | 19886.60 |
| 12 | Painting two coats of Asian/Burger or equivalent synthetic enamel paints over a coat of primer to Iron work after smoothening the surface by sand papering and filling the neet and holes with best quality of putty with cost, conveyanc, royalty, taxes of all materials labours etc. complete as per the direction of Engineer-in-Charge. | | | | |
| a) | Ground Floor | 31.14 | Sqm. | 174.66 | 5438.91 |
| 13 | Distempering two coats to walls with distemper of approved shade to give an even surface properly including cost conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer-in-charge, including the cost of all labour materials etc. complete | | | | |
| a) | Ground Floor | 242.16 | Sqm. | 115.48 | 27964.64 |
| 14 | Painting two coat to wall surface with weather paint of approved shade to give an even surface properly including cost conveyance, royalty taxes of all materials, labour, T & P required for the work etc. complete and as per direction of Engineer-in-charge, including the cost of all labour materials etc. complete | | | | |
| a) | Ground Floor | 210.72 | Sqm. | 126.97 | 26755.12 |
| 15 | Mild Steel tubular purlins with runners bracing for tubular trusses made out of ERW tubes of O.D.76.1 mm and 3.15 mm thick Grade YST 210 conforming to ISS no.1161/79 (3rd Revision) duly painted with red oxide primer. | 4889.04 | kg | 74.97 | 366531.33 |

| SL. NO. | ITEMS | QUANTITY | | UNIT | | RATE | Amount |
|------------------------------|--|----------|------|------|------|--------|-----------|
| 1 | 2 | 3 | | 4 | | 5 | 6 |
| 16 | Supplying fitting & fixing of Precoated Galvanized iron Profile sheet semi gloss of 1000mm width & total coated thickness 0.50mm in roof drilling hole in wind ties including fixing of ridges valleys, wind ties etc. complete including cost of sheet & all fitting (per 1 Sq. Mtr.) (Data for 9.3 sqm.) AR-page125/32 | 323.40 | Sqm. | 1 | Sqm. | 862.60 | 278964.84 |
| Total (AMOUNT PUT TO TENDER) | | | | | | | 24,55,135 |

16 Items(Sixteen items) only

Rate to be quoted in terms of % (Percentage) less or excess over the gross value of the tender amount as given above (both in words & figures in details). The percentage less or excess will be up to decimal point only.

Percentage of Excess or less :-

- (a) In Figures.....% Excess
- (b) In words.....% Excess
- (b) In Figures... % Less
- (c) In words % Less

Total No. of correction : _____

Total No. of Overwriting: _____

Total No. of Interpolations: _____

[Signature]
27/2/19

Jr. Engineer
LSDA, Serango

Junior Engineer
LSDA, Serango

[Signature]
27/2/19

Asst-Engineer
LSDA, Serango
Assistant Engineer
D A. Parlakhemund

[Signature]
27/2/19

Special Officer
LSDA, Serango
Special Officer
LSDA, Serango