

INTEGRATED TRIBAL DEVELOPMENT AGENCY,
PARALAKHEMUNDI:GAJAPATI
(SPECIAL DEVELOPMENT COUNCIL, GAJAPATI)

No. 362 /ITDA

Date.: 16.02.2019

TENDER CALL NOTICE NO.01/2018-19

The Project Administrator, ITDA, Paralakhemundi, District. Gajapati invites percentage sealed Tenders in the prescribed format for 1 no (One) of work to be eventually drawn up in P.W.D. F-2 forms in conformity with the Detailed Tender Call Notice from the eligible Govt. Registered Contractors of P.W.D./ N.H./Water Resources/ P.H.D./ R.D. Department , Govt. of Odisha/ C.P.W.D. belonging to the class as noted in respect of each work.

Sl. No	Name of the Work	Amount put to tender (Rs.)	Class of Contractor	Cost of Tender paper (Rs.)	EMD @ 1% (Rs.)	Time Period for Completion
1	Construction of Compound wall for Tribal Museum at Paralakhemundi under SDC Gajapati Khata No 181, Mouja Hatibadi, Gopinathpur.	* 36,35,058/-	"C" &"B"	6,000/-	37,000/-	06 (Six) Months

Date of Sale of Tender papers	:-	From 16.02.2019 to 26.02.2019 (From 10.00 A.M. to 4.00 P.M. on working days)only at Office of the P.A,ITDA,Paralakhemundi
Date of Receipt of Tender *	:-	From 16.02.2019 to 27.02.2019 (From 10.00 A.M to 5.00 P.M. on working days) only at Office of the P.A,ITDA,Paralakhemundi
Mode of Receipt of tender	:-	By Regd. Post with A/D, Speed Post only on working days only. No other mode will be accepted.
Date of opening of Tender **	:-	On 28.02.2019 at 11.00 A.M. at Office chamber of the P.A.,ITDA,Paralakhemundi

* In case it is declared by Govt. as a holiday the next working day will be treated

as the last date for receipt of Tender.

** In case it is declared by Govt. as holiday, the next working day shall be the date for opening of the Tender Paper which will be held as per Schedule.

The list of works with class of Contractor ,cost of tender paper and EMD required has been web hoisted in the website www.gajapati.nic.in.

This Tender is under two bid system

The Tender has been invited under two bid system i.e. **Technical Bid and Financial Bid**. The intending firm must submit in two separate sealed envelopes for each of the Items separately superscribing;

ENVOLPE NO. 1 : Subscribed by "**Technical Bid**":- All required documents.

ENVOLPE NO. 2 : Subscribed by "**Financial Bid**":- Quoted Rate in the format of Tender Schedule.

Both the "**Technical Bid & Financial Bid** " are to be placed in a third sealed envelope subscribed with; "**Tender Call Notice No. 01 /2018-19, Dated- 15.02.2019** "

Documents to be attached in the Tender bid cover:-

Tender should be accompanied with the following documents and these documents be placed inside the Technical Bid Envelope.

[1] E.M.D as required against the work should be enclosed alongwith the tender duly pledged in favour of the Project Administrator, ITDA, Paralakhemundi in shape of NSC/KVP/Term Deposit of any Nationalised Bank/Pas Book of Post office.

[After finalization of the Tender the E.M.D of the unsuccessful Tenderers will be refunded]

[1] Cost of tender paper (in shape of money receipt in case of direct purchase from the office.

[2] Photocopy of GSTIN certificate,

[3] Photocopy of Income Tax clearance certificate

[4] Photocopy of valid contract License

[5] Photocopy of Pan Card.

[6] Experience Certificate regarding the Construction of Boundary wall and others if any.

[7] No relation certificate

[8] Documents if any, issued by the competent authority exempting the Firm regarding submission of EMD.

[9] The supporting documents of having the concrete Mixture machine, water tanker, steel centring and shuttering materials and T & P etc.

[10] An affidavit about the Authenticity of Tender documents alongwith the Tender paper.

[11] Other relevant documents, if any

Condition 1:- The Engineering Contractors seeking exemption on EMD have to produce their original license at the time of opening of tender for entering of EMD exemption since they can be awarded maximum in three works in a financial year with such exemption.


Condition 2:- As per amendment to Para 3.5.5(V) of note 2 of OPWD code volume-1 by modification. Official memorandum No- 5288 dated 04.05.2016 of works Department Additional performance security shall be deposited by the successful bidder when the bid amount is unbalanced that is less than the estimated cost put to tender, in such an event , the successful bidder who have quoted less bid price/ rate than the

estimated cost put to tender , shall have to furnish the exact amount of difference cost i.e estimated cost put to tender (-)the quote as addl performance Security in shape of Post Office Bank Account(NSC/POTD account /KVP/Deposit receipt of schedule Bank) duly pledged in favour of Project Administrator, ITDA, Paralakhemundi within 07(Seven) days from the date of intimation about success of the tender.

1. The financial bid shall be opened by the tender committee as per the date, time and venue mentioned in the "Tender Call Notice" in presence of tenderers, whose technical bid will be qualified.

The photocopy of all documents should be duly attested by any Gazetted Officer are to be furnished along with the tender. The tenders without the above documents and EMD will be rejected. The Authority will not be responsible for any postal delay for receipt of Tender papers in this office. The Tenders will be opened on the date notified above in presence of tenderers or their authorised agents. The authority reserves the right to reject any or all tenders without assigning any reason thereof .The decision of the Tender Committee shall be final and binding.

The aforesaid notice shall be available in the District website-www.gajapati.nic.in after being hoisted by the DIO, NIC, Gajapati.


Project Administrator,
I.T.D.A.,Paralakhemundi

16/04/2019

Memo No:- 363 / 2019 ITDA,

Date.: 16.02.2019

Copy submitted to the Commissioner-cum-Secretary to Government, S.T & S.C.Development Department, Odisha, Bhubaneswar for favour of kind information.

Project Administrator,
I.T.D.A., Paralakhemundi

Date.: 16.02.2019

Memo No:- 364 / 2019 ITDA,

Copy submitted to The Additional Secretary to Government Planning & Convergence Department Odisha, Bhubaneswar for favour of kind information

Project Administrator,
I.T.D.A., Paralakhemundi

Date: 16.02.2019

Memo No:- 365 / 2019 ITDA,

Copy submitted to the Collector, Gajapati for favour of kind information and necessary action.

Project Administrator,
I.T.D.A., Paralakhemundi

Memo No:- 366 / 2019 ITDA ,

Date: 16.02.2019

Copy submitted to the Sub-Collector, Paralakhemundi/ Project Administrator, ITDA/ Gunupur/Koraput/Jeypore/ Nabarangapur/ Malkangiri/Rayagada/ Executive Engineer, M.I.Division, Gajapati/ Executive Engineer, R&B Division, Paralakhemundi , Gajapati/ All Block Development Officers of Gajapati District/All Tahasildars of Gajapati District/SDO,RWS & S,Paralakhemundi / All Local offices with a request to cause publication of the Notice in their Office Notice Board for information and wide circulation.

Copy to Office Notice Board of this office for information of all concerned for wide publication.

Project Administrator,
I.T.D.A., Paralakhemundi

Memo No :- 367 / 2019 ITDA,

Date: 16.02.2019

Copy forwarded to the D.I.O., NIC,Paralakhemundi for information and necessary action. He is requested to release the tender in the website for wide publication.

Project Administrator,
I.T.D.A., Paralakhemundi

Memo No :- 368 / 2019 ITDA,

Date: 16.02.2019

Copy to the Assistant Executive Engineer, ITDA / All Junior Engineers, ITDA, Head clerk, ITDA / Accountant, ITDA and Development Clerk of I.T.D.A, Paralakhemundi for information and necessary action.

Project Administrator,
I.T.D.A., Paralakhemundi

**Tender document for Construction of Compound wall for Tribal Museum at
Paralakhemundi**

TECHNICAL BID

1	Name of the Contractor	
2	Address for correspondence (with Telephone No/ Fax No with STD code, Mobile	
3	Cost of Tender Paper (inshape of Money Receipt in case of direct purchase for the office and in shape of DD in case it is downloaded from District Website)	
4	Photocopy of GSTIN Certificates	
5	Photocopy of Income tax clearance Certificate	
6	Photocopy of valid contract license	
7	Photocopy of PAN card	
8	Experience certificate regarding the Construction of boundary wall and others if any	
9	No relation certificate	
10	Documents if any, issued by the competent authority exempting the firm regarding submission of EMD	
11	Supporting documents having the concrete mixture machine , water tanker , steel centering and shuttering materials and T & P etc	
12	An affidavit about the authenticity of tender documents along with the tender paper	
13	Any other relevant documents if any	

Signature of the Tenderer

DRAFT TENDER SCHEDULE

Name of the Work:-Construction of Compound wall for Tribal Museum at Paralakhemundi under SDC Gajapati Khata No 181, Mouja Hatibadi, Gopinathpur.

1.Amount put to Tender:- 36,35,058/-

2.E.M.D. Required:- ₹ 36,400/-

3. Class of contractor :- "C" & "B"

4. Cost of Tender Paper:- ₹ 6000/-

5. Sale of bid document from -

16/02/19 to 26/02/19 (From 10.00 AM to 4.00 PM on working days)only

6. Receipt of bid document from- 16/02/19 to 27/02/19 (From 10.00 AM to 5.00 PM on working days)only

7. Date & time of opening of tender on-

28/02/19 at 11.00 AM at Office Chamber of the PA, ITDA, Paralakhemundi

8. Time required for completion: 6(Six) calendar Months

SL. NO.	ITEMS	UNIT	QUANTITY	RATE	Amount
1	2	4	7	8	9
1	Earth work in excavation of foundation trenches & Columns in all kinds of soil within all lead and lifts including dressing the sides, shoring (if necessary), bailing out water and leveling the bed and depositing the excavated materials away from the work site including all costs of labour rehandling if any sundries tools & plants required for the work etc complete as per direction of Engineer-in-Charge	1 Cum.	419.21 Cum.	261.71	109711.00
2	Filling in foundation and Plinth with sand well watered and rammed & dressed & level to proper gradient including all cost, conveyance, royalty taxes of all materials, Labour, rehandling if any, T & P required for the work etc. complete and as per direction of Engineer in Charge	1 Cum.	196.54 Cum.	421.98	82936.00
3	Cement concrete (1:3:6) with 4 cm. size crusher broken hard granite metals of approved quality including mixing with concrete mixture, lowering & laying in layers not exceeding 300 mm in depth, ramming compacting with mechanical Viberator to proper thickness, watering, curing for required period including all cost, conveyance, royalty taxes of all materials etc. complete & cost of all labour rehandling if any as per the direction of Engineer-in-Charge.	1 Cum.	58.20 Cum.	4342.20	252716.00
4	R R H G Stone masonry using H G. Stone free from weather skin greater than 0.0025 cum size in foundation and plinth with cement mortar (1:6) including watering and curing for required days with all cost, conveyance, royalty, taxes of all materials & all cost of labour, rehandling if any etc. complete as per the direction of Engineer-in-Charge.	1 Cum.	181.35 Cum.	3024.14	548428.00
5	Cement Concrete of prop((1:2:4) with 12mm size CBG chips of approved quality and from approved quarry including hoisting lowering and laying concrete in layers not exceeding 15cm thick to the required level, ramming and watering and curing etc. complete as per specification and direction of Engineer in -charge including cost, conveyance taxes and royalties of all materials with all cost of labour rehandling if any with T&P required for the work etc. complete as per direction of Engineer -in -charge	1 Cum.	5.60 Cum.	6019.27	33708.00
6	Rainforced cement concrete M-20 grade using 20mm and down graded size crusher broken hard granite chips of approved quality including mixing with concrete mixture, including hoisting and laying in position & compacting with vibrator to proper design section including cost, conveyance, royalty & taxes of all materials, all cost of labour, rehandling if any, inclusive of providing rigid & smooth centering and shuttering and dismantling the same after 28 days of casting disposing the materials away from the work site including watering, curing etc. complete as per direction of the Engineer-in-Charge				
a	Coloumn base Footing	1 Cum.	69.41 Cum.	5264.13	365383.00
b	Plinth Beam	1 Cum.	26.38 Cum.	5515.15	145490.00
c	Coloumn & Beam	1 Cum.	18.10 Cum.	10515.35	190328.00
d	Roof Slab	1 Cum.	0.78 Cum.	9194.11	7171.00
e	Top Finishing	1 Cum.	3.85 Cum.	9194.11	35397.00
7	Supplying HYSD/Tor steel reinforcement from SAIL,VIZAG STEEL OR TATA STEEL brand of required diameter of approved quality including Labour charges for cutting, bending, binding and tying the grills and placing in position including cost, conveyance & taxes of reinforcements confirming to ISI standard and binding wire 18 to 20 gauge and as per drawing, design etc complete inclusive all cost of labour, rehandling if any as per the direction of Engineer-in-Charge	1 Qtls.	130.37 Qtls.	6385.99	832542.00

Signature of Contractor

Project Administrator
ITDA, Paralakhemundi

	ITEMS	UNIT	QUANTITY	RATE	Amount
8	9" thick Flyash Bricks in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 kg/cm ² immersing the bricks in water not less than six hours before use in masonry including watering and curing for required period with all cost conveyance, royalty, taxes of all materials etc. all cost of labour, rehandling if any complete as per the direction of Engineer-in-Charge	1 Cum.	146.82 Cum.	4075.35	598343.00
9	16 mm thick cement plaster (1:6) over brick work including racking out joints finishing smooth with proper plumb and line watering curing for seven days with cost, conveyance, royalty taxes of all materials, all cost of labour, rehandling if any, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge.	1 sqm	1396.38 sqm	193.10	269641.00
10	20 mm thick cement plaster (1:6) over Stone masonry including racking out joints finishing smooth with proper plumb and line watering curing for required period with cost, conveyance, royalty taxes of all materials, all cost of labour, rehandling if any, T & P required for the work etc. Complete as per the direction of Engineer-in-Charge	1 sqm	465.00 sqm	206.00	95790.00
11	6 mm thick cement plaster with cement Mortar (1:4) to ceiling of roofs, stairs, landings, chajja Shelves, columns, beams and lofes etc including scrapping, cleaning and finishing the plastered surface smooth by using wooden floats to proper plumbs as per specifications including cost, conveyance, royalty of all materials etc complete as per the direction of Engineer-in-Charge	1 sqm	29.11 sqm	149.33	4347.00
12	Painting two coats with approved weather seal paint over a coat of primer over plastered surface including cost, conveyance all materials, labour and T & P etc complete as per the direction of Engineer-in-Charge	1 sqm	1493.33 sqm	91.81	137103.00
13	Painting two coats with approved enamel paint over a coat of primer with any approved paint over new steel surfaces etc complete as per the direction of Engineer-in-Charge	1 sqm	8.24 sqm	174.11	1435.00
14	Providing of M.S grill gates, with proper specified angle section, bars, fixing in proper position at work site including the cost, conveyance of all materials, all cost of labour T & P etc complete as per direction of Engineer-in-Charge	1 Kg	426.60 kg	91.49	39030.00
Total 14(Fourteen) items only				Amount Put to Tender	3749499.00

Rate to be quoted in terms of % (Percentage) less or excess over the gross value of the tender amount as given above (both in words & figures in details) The percentage less or excess will be up to decimal point only

Percentage of Excess or less :-

(a) In Figures.....% Excess

(b) In words.....% Excess

(b) In Figures.....% Less


(c) In words.....% Less


Total No. of correction : _____


Total No. of Overwriting: _____

Total No. of Interpolations: _____


10/02/19
JUNIOR ENGINEER
I.T.D.A., PARALAKHEMUNDI


10/12/19
ASSISTANT ENGINEER
I.T.D.A., PARALAKHEMUNDI


PROJECT ADMINISTRATOR
I.T.D.A., PARALAKHEMUNDI
12/02/19

Approved

DRDA, Gajapati
Paralakhemundi
16.02.19

Signature of Contractor

Project Administrator
ITDA,Paralakhemundi